

TWR-61561

# TECHNICAL EVALUATION MOTOR NO. 7 (TEM-07) INTERIM REPORT (60 day)

8 February 1991

# Prepared for:

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION GEORGE C. MARSHALL SPACE FLIGHT CENTER MARSHALL SPACE FLIGHT CENTER, ALABAMA 35812

Contract No.

NAS8-30490

DR. No.

5-3

WBS.No.

HQ601-20-10

ECS No.

1028



P.O. Box 707, Brigham City, UT 84302-0707 (801) 863-3511

(MACH-UN-100) ) THEMBICAL EVALUATION MUTTER HIS 7 (THEAT) THE FIRM HODDER (ThioRol COCL 218 COT. -) 100

W01-30261

unclas 63/20 005774) Technical Evaluation Motor No. 7 (TEM-07) Interim Report (60 day)

Prepared by:

Certification Planning Systems Engineer

Approved by:

Certification Planning

Supervisor

ECS# SS1028

Major contributors to this report were:

Instrumentation: D. South

Case/Leak Check/Seals: T. Swauger, R. Ash, G. Abawi

Insulation: J. Passman, S. Manz

Nozzle: R. George, R. Lange, F. Weiler

Joint Protection Systems: C. Prokop, K. Rees

Ballistics/Mass Properties: A. Drendel

Aero/Thermal: R. Buttars, E. Mathias, D. Ruddell

Structural Analysis: M. Fairbourn, D. Bright

Postfire Hardware Evaluation: J. Curry

Photo Instrumentation: C. Larsen

#### ABSTRACT

Technical Evaluation Motor No. 7 (TEM-7) was a full scale, full-duration static test firing of a high performance motor (HPM) configuration solid rocket motor (SRM) with nozzle vectoring. The static test fire occurred on 11 December 1990 at the Thiokol Corporation Static Test Bay T-97.

This interim test report documents the procedures, performance and results available through 22 January 1991. Critical post test hardware activities and assessment of test data are not complete in time to support a complete final test report submittal 60 days after the test date. A complete final test report will be submitted no later than 19 April 1991.

Included are a presentation and discussion of the TEM-7 performance, anomalies, and test result concurrence with the objectives outlined in CTP-0107 Revision A, Space Shuttle Technical Evaluation Motor No. 7 (TEM-07) Static Fire Test Plan.

# CONTENTS

Secti	<u>on</u>	<u>Page</u>
1.0	INTRODUCTION	3 . 4 . 12 . 13 . 13 . 13
2.0	TEST OBJECTIVES	. 20
3.0	EXECUTIVE SUMMARY	. 22
4.0	INSTRUMENTATION	. 23
5.0	PHOTOGRAPHY	. 24 . 24 . 24
6.0	TEST RESULTS	. 27 . 27 . 29 . 29 . 36 . 36 . 37 . 43 . 43 . 46 . 47 . 48 . 48 . 52

# CONTENTS (cont)

Secti	ion																		<u>P</u>	age
	6.7 BAL	LISTICS/MAS	S PRO	PEF	TI	ES	P	EF	REC	RI	IAN	1CE	3			٠		•	•	53
	6.7.1	Introduct	ion .													•	•	•	•	53
	6.7.2		s															•	•	23
	6.7.3		ns/Re	con	ıme	nd	lat	ic	ns	3							•			53
	6.7.4	Observati	ons .																	54
	6 0 CTA	TIC TEST SU	PPORT	' EC	ÙΙ	PM	ΙEΝ	Т											•	80
	6.8.1	Introduct	ion .	,														•	•	80
	6.8.2	Observati	ons .											•	•	•	•	•	•	80
7 0		RIE DOCUMENT	c					_								•				81

# FIGURES

Figure		<u>Pa</u>	age
	1 1	TEM-7 Test Article	5
Figure Figure		Stiffener Stub Outer Ligament Cracks and	_
rigure	1 2.	Instrumentation	6
Figure	1-3.	Stiffener Stub Outer Ligament Cracks and	7
<b>3</b>		Instrumentation	,
Figure	1-4.	Stiffener Stub Outer Ligament Cracks and	8
		Instrumentation	9
Figure		TEM-0/ Field Joint Configuration	
Figure	1-6.	Configuration	10
Figure	1 7	Cowl Liner/Flex Bearing Thermal Protector Area	
rigure	1-7.	Configuration Changes	15
Figure	1-8.	Improved Nose Cowl Assembly Method	16
Figure		Fixed Housing and Boot Cavity	
119	_	Instrumentation	17
Figure	1-10.	Thrust Vector Actuation (TVA) System	18 26
Figure		T-97 Photography Coverage - TEM-07	30
Figure		HPM Field Joint	31
Figure		Clevis Joint Filler Putty Layup	32
Figure		Assembled HPM Field Joint	Ŭ-
Figure	6-4.	Configuration - Putty Layup	33
	c =	Ignition System Components and Seals	49
Figure		Standard HPM Igniter System	50
Figure Figure		S&A Device Configuration	51
Figure		TEM_7 Predicted and Measured Pressure	
rigure	0 0.	at 65 Deg F	61
Figure	6-9.	TEM-7 Reconstructed and Measured Pressure	
		at 65 Deg F	62 63
Figure	6-10.	Reconstructed Vacuum Thrust at 65 Deg. F	03
Figure	6-11.	Comparison of Reconstructed and Measured	64
		Aft-End Pressure	69
Figure		TEM-7 Igniter Reconstructed at 80 Deg. F	
Figure	6-13.	within Specification Limits	70
Figure	6_1/	TEM-7 Igniter Pressure vs. Head-End and Nozzie	
rigure	0-1	Charaction Pressure	71
Figure	6-15.	TEM-7 Measured Head-End and Nozzle Stagnation	
rigaro	. •	Pressure Time Histories	72
Figure	6-16.	TEM-7 Waterfall Plot for PNCACOO1	74
Figure	6-17.	TEM-7 Maximum Oscillation Amplitudes for	75
_		PNCAC001 1-L Acoustic Mode	, ,
Figure	6-18.	TRM-/ Maximum Obcititación impe-	76
		PNCACOO2 2-L Acoustic Mode	, ,
Figure	6-19.	Specification Limits	77
		Specification nimites	

## TABLES

<u>Table</u>			<u>Page</u>
Table Table Table Table Table Table Table	5-1. 6-1. 6-2. 6-3. 6-4.	TEM-07 Segment History	37 38 38 39
Table	6-6.	Results	. 55
Table	6-7.	Burn Rate Data Comparison Subscale to	. 66
Table	6-8.	Historical Three Point Average Thrust and Pressure Rise Rate Data	. 67
Table	6-9.	Measured SRM Ignition Performance Data	. 68
Table	6-10.	Maximum Pressure Oscillation Amplitude Comparison	

#### 1.0 INTRODUCTION

Technical Evaluation Motor No. 7 (TEM-7) was successfully static test fired at 1300 hours on 11 December 1990 at the Thiokol Corporation Static Test Bay T-97. The ambient temperature at the time of the test was 43.7 °F and the propellant mean bulk temperature was 65 °F. Ballistics performance values were within the specified requirements.

TEM-7 was a full scale, full-duration static test fire of a high performance motor (HPM) configuration solid rocket motor (SRM). TEM-7 was the first full scale test motor on which all segments were more than five years old and the first TEM static test motor with nozzle vectoring. The TEM-8 static test motor will also be vectored. The TEM-7 test arrangement included the Modified Aft End Heating System (MAEHS) normally used for static tests with vectored nozzles plus a nozzle to case joint heater normally used for TEM static tests.

The primary purpose of TEM static tests is to recover SRM case and nozzle hardware for use in the RSRM flight program; however, TEM static tests also provide windows of opportunity to evaluate or certify various design, process, and supplier issues for the RSRM Accordingly, TEM-7 was the first full scale flight program. static test for qualification of North American Rayon Corporation (NARC) rayon in all nozzle carbon cloth phenolic (CCP) liners. Two additional full scale nozzles will be statically tested for qualification of the NARC rayon as outlined in the second source Low cost nozzle improvements, rayon program plan, TWR-18965. previously incorporated into the TEM-6 static test, qualified on TEM-7 included a change in the carbon cloth phenolic (CCP) liner ply angle of the cowl, improved inner and outer boot ring phenolic cure cycles, and an extended belly band flexible bearing protector design.

Inspection and instrumentation data indicate that the TEM-7 static test firing was successful. Instrumentation measurements consisted of forward and aft end chamber pressure; igniter chamber pressure; forward and aft pressure chamber pressure oscillations; stiffener stub strains; nozzle components temperatures and strain; temperature for deluge control; nozzle deflections; nozzle boot cavity temperature and pressure; plume radiation measurements; test stand water deluge pressure; and timing.

Overall, the postburn condition of the NARC rayon nozzle liners was very good (TWR-61490). Only two small, shallow wash areas were found on the aft exit cone liner, but no surface ply lifting was observed. The erosion of the throat and throat inlet rings was smooth with the typical rippled erosion pattern occurring on the aft 6 inches of the throat ring (0.1 inch deep maximum). The post burn mean throat diameter was 56.07 inches.

This is within the historical database of RSRM/HPM throat diameters. The preliminary throat erosion rate was 9.17 mils/sec. Typical minor wash areas (0.1 inch deep maximum) were observed on the forward portions of the nose cap. The cowl ring erosion was smooth and did not exhibit the typical wash areas seen on RSRM (0 degree ply wrap) cowls.

All postfire flow surface gaps between phenolic components were uniform around the circumference and were within the historical database. There was no indication of movement of the nose cap and the bondline between the cowl and outer boot ring was still intact.

TEM-7 was instrumented with four (4) aft end chamber pressure transducers installed through special instrumentation holes drilled through the fixed housing and phenolic insulation. TEM-6 also contained this arrangement. The objective of this instrumentation was to obtain aft end chamber pressures for ballistics modelling and pressure oscillations.

On TEM-7, aft end pressure plots showed spikes shortly after ignition. Upon removal of the pressure transducers, the ends were found charred and heat effected. After removal of the nozzle, the fixed housing phenolic insulation was found to be shifted forward (unbonded) approximately 0.20 inch from the metal fixed housing. After nozzle disassembly, the fixed housing phenolic insulation was found to be almost 100% adhesive unbonded from the metal.

By comparison, TEM-6 aft end pressures were as predicted, with slag plugging the holes randomly after T+20 sec. Plugging of the instrumentation holes was expected. The TEM-6 pressure transducers were found to be in excellent condition upon removal with no indications of leakage or gas flow.

TEM-7 was configured with a bearing protector in which the belly band was lengthened and thickened. The belly band was extended to place the region of maximum erosion in the thickened portion of the bearing protector. On TEM-7 the belly band was additionally thickened to accomodate potential for increased erosion due to enlarged cowl vent holes. After removal of the TEM-7 fixed housing from the bearing, the bearing protector was found to be deeply eroded in the areas where gas impinged from the cowl vent holes. Maximum erosion was centered in this lengthened and thickened belly band region of the bearing protector.

Preliminary observations indicate that performance of the improved cowl assembly process (Joint #2) was excellant.

TEM-7 postfire inspection procedures followed TWR-60273 and TWR-61209.

# 1.1 TEST ARRANGEMENT AND FACILITIES

The TEM-7 static test arrangement was assembled in accordance with Drawing 2U129760. T-97 was equipped with a water deluge system and a  $\rm CO_2$  quench. The test motor included an SRB aft skirt assembly which contains the TVC subsystem and the heat shield installation. The Thrust Vector Actuation (TVA) System is comprised of two SRB actuators and two Hydraulic Power Units (HPU) located in the aft skirt. The HPU Ground Test Controller, HPU Manual/ Automatic Panel (MAP) and the Ascent Thrust Vector Control units (ATVC) serve as the control units for the TVC subsystem.

# 1.2 TEST ARTICLE DESCRIPTION

The TEM-7 test assembly was in accordance with Drawing 7U76879. The motor was instrumented to provide data to satisfy the test objectives. An overall view of the test article is shown in Figure 1-1. A TEM-7 drawing tree is included in Appendix A.

TEM-7 consisted of HPM-configuration motor segments which were fabricated and loaded with propellant more than five years before the static test fire on 11 December 1990. A listing of each segment, segment flight identification, cast date, and storage and transportation history is shown in Table 1-1.

TEM-07 Segment	Forward	Fwd Ctr	Aft Ctr	Aft
Flight Identification	SRM 28B	SRM 28B	SRM 28B	SRM 26A
Casting Date	24 Sep 85	21 Oct 85	14 Oct 85	17 Jul 85
Shipped to KSC	31 Jan 86	10 Jan 86	7 Jan 86	26 Dec 85
Shipped to Thiokol Arrived at Thiokol	27 Mar 87 10 Apr 87	18 Jan 89 25 Jan 89	25 Jul 89 31 Jul 89	24 Mar 88 10 Apr 88
Shipped to KSC	10 Jun 87	-	_	-
Shipped to Thiokol	22 Feb 89 29 Feb 89	-	-	-

Table 1-1. TEM-07 Segment History

The High Performance SRM static test motor consisted of a lined, insulated, segmented rocket motor case loaded with solid propellant; an ignition system complete with electro-mechanical safety and arming device, initiators and loaded igniter; movable nozzle with flexible bearing and exit cone. For this test, the nozzle was vectored.

The assembled static test motor was approximately 116 feet in length and 12 feet in diameter. The test item configuration was controlled by released engineering drawings (reference TEM-7 Drawing Tree) and the test plan, CTP-0107, Revision A. Deviations configuration were processed through the configuration control system and approved by the Integration Engineer, Program Manager and NASA, and will be documented in the final test report.

#### Case/Seals 1.2.1

The Case consisted of 11 individual weld-free segments: forward dome, six cylinder segments, the ET attach segment, two stiffener segments and the aft dome. The 11 segments were preassembled into four subassemblies to facilitate propellant casting.

The four loaded assemblies were the forward segment assembly forward center segment 7U76899), the (Drawing (Drawing 1U52566), the aft center segment assembly (Drawing 1U52566), and the aft segment assembly (Drawing 7U76882). segments were joined by means of tang and clevis field joints, which in turn, were held in place by pins.


Stiffener rings were installed on both flanges of the aft stiffener cylinder (1U50185-06, S/N 027). These flanges have outer ligament cracks:

- At 240 degrees on aft stub
- At 276 degrees on aft stub (saw cut through) 2)
- At 278 degrees on aft stub 3)
- At 280 degrees on aft stub 4)
- At 282 degrees on aft stub 5)
- At 232 degrees on forward stub 6)
- At 288 degrees on forward stub (not instrumented)

Instrumented outer ligament cracks and instrumented referee holes are illustrated in Figures 1-2, 1-3 and 1-4.

Systems tunnels were removed from the aft center segment and partially removed from the aft segment for this test.

The nozzle to case joint was formed by bolting the HPM nozzle fixed housing into the aft dome with 100 axial bolts. The field joints had a standard HPM insulation configuration as shown in Figure The nozzle to case joint had the standard HPM nozzle joint insulation configuration as shown in Figure 1-6.



TWR-61561

PAGE

DOC NO.

SEC

VOL


5

REVISION \_

# Thickol CORPORATION

SPACE OPERATIONS

REVISION




Note: All gages oriented to measure hoop strains

Figure 1-2. Stiffener Stub Outer Cracks and Instrumentation

DOC NO.	TWR-61561		VOL
SEC	PAGE	6	

REVISION




Note: All gages oriented to measure hoop strains

Figure 1-3. Stiffener Stub Outer Ligament Cracks and Instrumentation

DOC NO.	TWR-61561	VOL
SEC	PAGE	7

# Thickol CORPORATION






Note: All gages oriented to measure hoop strain

Figure 1-4. Stiffener Stub Outer Ligament Cracks and Instrumentation

DOC NO.	TWR-615	61		VOL
SEC	•	PAGE	8	

REVISION \_\_\_\_






Figure 1-6. TEM-07 (HPM Modified) Nozzle-to-Case Joint Configuration

DOC NO.	TWR-61561	VOL
SEC	PAGE	10

The assembly and joint configuration were as follows:

- A. Forward segment and forward center segment were mated to form the forward field joint. The forward center segment and aft center segment were mated to form the center field joint. The aft center segment and aft segment were mated to form the aft field joint. The field joints which connected these segments were configured with:
  - o Tang and clevis with long pins (Drawing 1U51055), custom-fit shims (Drawing 1U51899), and hat band pin retainers (Drawing 1U82840).
  - o Standard HPM insulation configuration with putty joint filler (STW4-3266) as shown in Figure 1-5.
  - o Primary and Secondary O-rings were Fluorocarbon (STW4-3339).
  - o Leak check port plugs (Drawing 1U100269)
  - o Improved field joint heater (Drawing 1U77252).
  - o Baseline TEM field joint protection system (Drawing 7U77328).
- B. Factory joints were configured with the following:
  - HPM tang and clevis hardware design.
  - o Insulation overlaid and cured over interior of the joint.
  - o HPM pin retainer centered over the short (HPM) pins. Standard shim clips were used between the clevis outer leg and the tang OD.
- C. The nozzle to case joint was configured with:
  - o Primary (larger diameter RSRM) and secondary 0-ring seals were Fluorocarbon (STW4-3339).
  - o Standard HPM nozzle joint insulation configuration with putty joint filler (STW4-3266) as shown in Figure 1-6.
  - o RSRM configuration ultrasonic preload axial bolts installed in accordance with dwg 7U76882.
  - o MS16142 vent ports at 15, 105, 195 and 285 degrees in the fixed housing (7U76865-02) upstream of the primary O-ring.

- o Adjustable vent port plugs and closure screw (Drawings 1U76425 and 1U50159).
- o Leak check port plug (Drawing 1U100269)
- o Redesigned nozzle to case joint heater (7U77118-04)
- D. Igniter to forward dome joint was configured with:
  - o Primary and secondary seals of the outer gasket (Drawing 1U51927) are fluorocarbon.
  - o Improved igniter to case joint heater (Drawing 1U77253).
  - o Putty joint filler (STW4-3266).
  - o Ultrasonic bolts (Drawing 1U76598) inner and outer bolt circle

Corrosion protection consisted of full external paint and a film of grease applied as specified in Drawing 7U76881 and STW7-3688 (including O-rings, sealing surfaces, and pin holes).

# 1.2.2 Internal Insulation/Liner/Inhibitor

The internal insulation system included case acreage insulation, joint insulation and propellant stress relief flaps. The insulation material used for these components was an asbestos silica filled acrylonitrile butadiene rubber (NBR) (STW4-2621). Carbon fiber filled ethylene propylene diene monomer (CF/EPDM) (STW4-2868) was bonded to the NBR in a sandwich type construction under the propellant stress relief flaps in both center segments. CF/EPDM was also used in sandwich construction in the aft dome. The CF/EPDM was installed to reduce the erosion of the insulator near the submerged nozzle in the aft dome and under the stress relief flaps in the center segments.

The liner material specified in STW5-3224 was an asbestos-filled carboxyl terminated polybutadiene (CTPB) polymer which bonded the propellant to the internal insulation in the SRM. The forward facing full web inhibitors were made of NBR. They were located on the forward end of the center and aft segments. The aft facing partial web castable inhibitors were made of a material (STW5-3223) similar in type (CTPB polymer) to the liner. They were HPM configuration and were located on the aft end of the forward and center segments.

Field joints and nozzle to case joint are HPM configuration and were filled with putty and tamped following assembly to repair defects and reduce the potential for blow holes.

# 1.2.3 Propellant

SRM propellant, TP-H1148 (STW5-3343), is a composite type solid propellant, formulated of polybutadiene acrylic acid acrylonitrile terpolymer binder (PBAN), epoxy curing agent, ammonium perchlorate oxidizer and aluminum powder fuel. Approximately 0.21% by weight (exact amount determined by standardization) of burning rate catalyst (iron oxide) was added to achieve the targeted propellant burning rate of 0.368 in/sec at 625 psia and 60 °F (TWR-19121 and TWR-19838).

The propellant grain design consisted of an eleven-point star with a smooth bore to fin cavity transition region that tapered into a circular perforated (CP) configuration in the forward segment (Drawing 1U52565). The two center segments (Drawing 1U52566) were double-tapered CP configurations and the aft segment (Drawing 1U52757) was a triple-taper CP configuration with a cutout for the partially submerged nozzle.

# 1.2.4 Ignition System

The SRM ignition system was a modified HPM igniter assembly (Drawing 1U50776). It contained a single nozzle, steel chamber, external and internal insulation, and solid propellant, TP-H1178 (STW5-2833), igniter containing a case bonded 40-point star grain.

The forward mounted solid rocket type igniter (Drawing 1U50776) was modified with a  $\rm CO_2$  quench port. Ultrasonically torqued bolts fastened the igniter adapter to the igniter chamber. A286 bolts in the igniter adapter to case joint were replaced with higher strength MP159 bolts which were ultrasonically preloaded to a higher level.

A Safe and Arm (S&A) device (1U52295-04) which utilizes Krytox grease to lubricate the Barrier-Booster shaft O-rings was installed on the igniter.

Velostat or pink poly plastic sheets were wrapped and tightly sealed around the forward thrust adapter to simulate the thermal protection provided to the igniter and S&A by flight configuration.

# 1.2.5 Nozzle/TVC

The nozzle assembly (Drawing 7U76738) was a partially submerged convergent/divergent movable design with an aft pivot point flexible bearing (Drawing 1U52840). The phenolic liners were RSRM configuration with exceptions defined by the Low Cost Improvement Program Plan TWR-19524B. All metal hardware was RSRM except for the fixed housing which was HPM modified configuration to mate with the HPM aft segment.

The nozzle incorporated North American Rayon Corporation Corporation rayon into all carbon cloth phenolic liners (Drawings 7U76736, 7U76608, 7U76609, 7U76865, 7U77266, 7U77267, 7U77310).

The nozzle included changes in accordance with Low Cost Improvement Program Plan TWR-19524B and MSFC directives as follows:

- o Minus 50 degree ply angle change on cowl (Drawing 7U76609) second wrap
- o Full cure on CCP first wrap outer boot ring (Drawing 7U76608)
- o Delayed pressure cure on glass cloth phenolic (GCP) inner boot ring (Drawing 7U76608)
- o Bearing protector thickness/location modification (Drawing 7U76864) as shown in Figure 1-7
- o Improved nose to cowl assembly process (Figure 1-8)
- o Boot cavity pressure (Drawings 7U76827, 7U76983) and temperature measurement instrumentation (Figure 1-9)
- o Fixed housing pressure (Drawing 7U76902) measurement instrumentation (Figure 1-9)

The 36 vent holes in the cowl were increased in size from a nominal 0.312 inch diameter to a 0.375 inch diameter to alleviate boot cavity differential pressure. Supporting analyses for this change were documented in TWR-60857, Cowl Vent Hole Study and TEM-02 nozzle boot cavity pressurization. The flexible bearing protector (Drawing 7U76864) was thickened in the belly band region from a 0.67 inch minimum to a 1.0 inch minimum to accommodate any potential for increased erosion due to the larger vent holes.

Four MS-16142 type vent ports were machined into the nozzle fixed housing (7U76865-01) forward of the primary O-ring to facilitate venting of the cavity between the joint putty and the primary O-ring when assembling the nozzle to the case.

The nozzle-to-case joint was assembled with RSRM axial bolts with preload measuring capability. The assembly preload was a nominal 120,000 lbs.


The Linear Shaped Charge was not added to the aft exit cone (Drawing 7U77267) assembly for this test.

The axial test motor included an SRB aft skirt assembly identified on MSFC-NASA Drawing 14A30649-02. The aft skirt assembly contained the TVC subsystem and the heat shield installation.

The Thrust Vector Actuation (TVA) System (Figure 1-10) was comprised of two SRB actuators and two Auxillary Power Units (APU) located in the aft skirt.

The APU Ground Test Controller, APU Manual/Automatic Panel (MAP) and the Ascent Thrust Vector Control units (ATVC) served as the control units for the TVC subsystem.





Ply Angle

Was: 0 deg Now: -50 deg

Figure 1-7. Cowl Liner/Flex Bearing Thermal Protector Area Configuration Changes

REVISION	TWR-615	61 vo
	SEC	PAGE 15

Current Assembly Process

Improved Assembly Process

Guide Pin

Radial Bondline Backfilled

With RTV

Assembly

Fixture

Fixture

Guide Pin

Assembly

Fixture

Fixture

Axial Bondlines

2U65040-01

Assembly

Fixture

Fixture

Figure 1-8. Improved Nozzle Cowi Assembly Method

PAGE

16

REVISION \_\_




Figure 1-9. Fixed Housing and Boot Cavity Instrumentation

DOC NO. TWR-61561 VOL.

SEC PAGE 17

REVISION \_

REVISION




Figure 1-10. Thrust Vector Actuation (TVA) System

TWR-61561

DOC NO.

SEC

VOL

18

PAGE

#### 1.2.6 Leak Check Port Plugs

Leak check port plugs (1U100269-03) with the Nylock locking feature were installed in the leak check ports of all three field joints and the nozzle to case joint.

# 1.2.7 Adjustable Vent Port Plugs

Adjustable vent port plugs with the Nylok locking feature (1076425-03 and -02) and closure plugs (Drawing 1050159) were installed in the four RSRM vent ports of the nozzle fixed housing.

# 1.2.8 Joint Protection Systems

<u>Field Joint Protection Systems</u> Field joint heaters closeout (Drawing 7U77328, static test only) consisted of cork strips retained with Kevlar straps (TEMs 2, 3, 4 and partial 5 and 6). The external joint temperatures were sensed by two sensor assemblies mounted adjacent to the heater. Each assembly contained two resistance temperature detector (RTD) sensors.

Joint Heaters Improved field joint heaters (Drawing 1U77252), igniter to case joint heater (Drawing 1U77253) and nozzle to case joint heater (Drawing 7U77118) were installed as shown in Drawing 7U77328. These heaters consisted of redundant, chemically etched, foil circuits which are superimposed upon one another and laminated in polyamide plastic sheets. The underside Kapton surface of the field joint and nozzle to case joint heaters was coated with a pressure sensitive adhesive. This adhesive provided bonding to the case during assembly. The lead wires extended from the heaters and were terminated in electrical connectors.

<u>Power Cables</u> RSRM joint protection system (JPS) power cables (1U76702-01, 1U76702-02, 1U76703-01, 1U76703-02, 1U76704-01, 1U76704-02, 1U76705-01, 1U76705-02, 1U76706-01 and 1U76706-02) were installed to provide 208 VAC to the RSRM field joint and igniter-to-case joint heaters.

#### 2.0 TEST OBJECTIVES

The TEM-7 test objectives of CTP-0107 Revision A were derived from the objectives of System Test Summary Sheet TGX-21.6 to satisfy the requirements of Contract End Item (CEI) Specification CPW1-3600A, dated 3 August 1987.

Qualification objectives of this test were as follows:

- A. Certify North American Rayon Corporation (NARC) rayon for use in nozzle carbon cloth phenolic (CCP) liners (CPW1-3600A para. 3.2.1.4.13, 3.3.6.1.2.7, 3.3.6.1.2.8).
- B. Certify nozzle inner boot ring cure cycle improvement (CPW1-3600A para. 3.3.6.1.2.8).
- C. Certify nozzle outer boot ring cure cycle improvement (CPW1-3600A para. 3.3.6.1.2.8).
- D. Certify the nozzle cowl ring with an ablative liner ply angle change (from 0 deg to -50 deg) (CPW1-3600A para. 3.2.1.4.13, 3.3.6.1.2.8)
- E. Certify the improved nozzle bearing protector (CPW1-3600A para. 3.3.6.1.2.8).

Other test objectives included:

- F. Recover case and nozzle hardware for RSRM flight and static test programs.
- G. Obtain data on the effect of five year storage of loaded SRM case segments upon motor ignition and performance.
- H. Demonstrate the performance of an improved nose assembly to cowl assembly process for the nozzle (CPW1-3600A para. 3.2.3, 3.2.3.1, 3.3.1.1).
- I. Demonstrate the performance of increased cowl vent hole size (0.375 in. nominal diameter) for reducing boot cavity delta pressure (CPW1-3600A para. 3.3.6.1.2.8).
- J. Obtain additional data on the low frequency chamber pressure oscillations in the motor forward end and correlate with chamber pressure oscillation measurements in the motor aft end.
- K. Obtain additional data on chamber pressure drop down the bore by the use of aft end pressure transducers.

- L. Obtain additional data on cowl boot cavity/aft end (fixed housing) pressurization and temperature.
- M. Obtain additional data on the performance of the aft stiffener segment with known outer ligament cracks in the stiffener stubs.
- N. Obtain thermal radiation data from the nozzle plume for the ASRM program.

#### 3.0 EXECUTIVE SUMMARY

Inspection and instrumentation data indicate that the TEM-7 static test firing was successful overall. Data was gathered at instrumented locations during pretest, test, and post-test operations. The information assembled from the test procedures has supplied valuable knowledge and understanding about the performance of the HPM and RSRM design components utilized in TEM-7.

Damage to the improved nozzle bearing protector and flex bearing resulted in failure to demonstrate acceptable performance of increased cowl vent hole size (0.375 in. nominal diameter).

The separation of the nozzle fixed housing phenolic insulation from the metal fixed housing did not cause any noticeable performance problems. The aft end pressure transducers and strain gages provided valuable data which will be helpful in the investigation of this anomaly.

Investigations are being conducted to understand these anomalies and the phenomena which caused them. The final test report, TWR-17659, will contain conclusions and recommendations for resolution of these conditions.

#### 4.0 INSTRUMENTATION

#### 4.1 INTRODUCTION

TEM-7 instrumentation measurements consisted of forward and aft end chamber pressure; igniter chamber pressure; forward and aft pressure chamber pressure oscillations; stiffener stub strains; nozzle components temperatures and strain; temperature for deluge control; nozzle deflections; nozzle boot cavity temperature and pressure; plume radiation measurements; test stand water deluge pressure; and timing. Boot cavity temperature and pressure and aft end chamber pressure measurements were made for a second time on the TEM program. New improved stand-alone units with thermocouples TEM-7 was instrumented to gather were used for the first time. data on cracked stiffener stub holes as a follow up on data gathered on FSM-1. The metal component parts on the nozzle using NARC material were instrumented with temperature sensors and strain gages. Plume radiation measurements were taken again to enhance data gathered on FSM-1.

# 4.1 OBSERVATIONS

Forward pressure measurements were nominal, but aft end pressure measurements dropped off unexpectedly at T+2 seconds. The pressure transducers were heat effected as a gas path developed in the fixed housing insulation liner. Strain gages near the pressure transducers confirmed the unbond which occurred to the fixed housing insulation. The data from pressure gages and strain gages gave a time history of the unbonding sequence. All other strain gages and temperature sensors on the nozzle components performed and recorded no anomalies.

The instrumented stiffener stub holes strain gages all recorded data except for the lone referee strain gage mounted inside a stiffener stub hole.

The installed pressure transducers in the boot cavity and thermocouple were erratic. One pressure transducer recorded data until T+20 seconds and the other failed. The thermocouple data were erratic throughout the firing, but did demonstrate the increased temperature into the boot cavity resulting from increased vent hole diameters.

Temperature data were nominal. The ambient temperature was 43.7 °F and the propellant mean bulk temperature was 65 °F at T-0 (ignition). Joint and case temperature sensors all performed nominally.

Aft skirt and nozzle positioning measurements all performed as expected.

One of the twenty-two radiometers failed prior to the firing, but all other sensors provided very good data for plume radiation studies.

#### 5.0 PHOTOGRAPHY

Photographic coverage was required to document the test, test configuration, instrumentation, and any anomalous conditions which may have occurred. The TEM-7 photographs and video tapes are available from the Thiokol Corporation Photographic Services Department.

#### 5.1 STILL PHOTOGRAPHY

Still color photographs of the test configuration were taken before, during, and after the test. Photographs were taken of joints each 45 deg minimum and at anomalous conditions.

#### 5.2 MOTION PICTURES

Color motion pictures of the test were taken with nine high-speed cameras, two real-time documentary cameras, and four video cameras. Documentary motion pictures are recorded on roll 8330, high-speed motion pictures on roll 8331, and videotape on Toll8 through T-0121. Cameras are listed in Table 5-1. The camera setup is shown in Figure 5-1.

Table 5-1. Photography and Video Coverage

Camera	Station	Location	Type	Coverage
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	7 1 2 2 2 3 3 4 4 4 5 7 7	Thrust Block No. Fwd. Barricade No. Fwd. Barricade No. Aft Barricade No. Aft Barricade No. Aft Barricade So. Aft Barricade So. Aft Barricade So. Center Barricade So. Center Barricad So. Center Barricad Thrust Block Thrust Block Thrust Block	e HS	Center Aft & N/C Joints Aft Case, Nozzle & Plume Nozzle, 200 ft Plume

CODE:			
HS	_	9 each	300 PPS
no	-		0.4 DDC
Doc	_	2 each	24 PPS
Video	_	4 each	Real Time






Figure 5-1. T-97 Photography Coverage—TEM-07

REVISION		DOC NO.	TWR-61561	VOL
		SEC	PAGE	26

#### 6.0 TEST RESULTS

#### 6.1 CASE PERFORMANCE

#### 6.1.1 Introduction

Case assembly procedures proved adequate, and chamber pressure was contained during the static test.

# 6.1.2 Observations

## 6.1.2.1 Forward Field Joint

The TEM-7 forward field joint was disassembled on 16 January 1991. Light corrosion was observed in and around the leak check port hole and on the case at the joint heater region at 280 through 294 degrees. Typical pin hole slivers were found intermittently around the circumference of the clevis and tang pin holes. This is caused by installation of the pins at assembly. No anomalous conditions were observed.

# 6.1.2.2 Center Field Joint

The TEM-7 center field joint was disassembled on 14 January 1991. The condition of the joint was nominal. No corrosion was observed on the tang or clevis joints. Typical pin hole slivers were found intermittently around the circumference of the clevis and tang pin holes. This is caused by installation of the pins at assembly. The leak check plug and port were in nominal condition.

# 6.1.2.3 Aft Field Joint

The TEM-7 aft field joint was disassembled on 10 January 1991. No corrosion was observed on the tang or clevis joints. Pin hole slivers were found at 48, 50, 86, 88 and 228 degrees. This is caused by installation of the pins at assembly. Before port hole assessment the joint had shifted approximately 0.5 inch (pinholes were misaligned by approximately 0.5 inch at 0 degrees). The putty apparently extruded into the through hole when the joint shifted because no trace of putty was found on the clevis between the primary and secondary 0-rings. A preliminary PFAR was submitted since this condition is outside the engineering limits.

# 6.1.2.4 Cracked Stiffener Stub Holes

Special Issue (TWR-61209 Paragraph 3.2.1 Item 1)

All seven cracked stiffener stub holes were visually examined for new cracks and/or deformation. On several holes (240, 278 and 280 degrees) deformation was noted to exist on the aft face of the flange (near the hole). It was determined that this condition was a result of a previous usage and not a result of this test. No new cracks were detected by visual inspection. A gouge was found on the 240 degree hole on the aft flange. The gouge was located at approximate center of the flange cross section and raised metal exists.

# 6.2 CASE INTERNAL INSULATION PERFORMANCE

## 6.2.1 Introduction

The four TEM-7 segments had been insulated and cast with propellant more than five years before the TEM-7 static test.

Field Joint Assembly The case insulation of the three HPM-configuration field joints consisted of asbestos-silica-filled NBR (Figure 6-1). Prior to mating, the joints were inspected per STW7-2831, REV NC, the flight motor insulation criteria for the HPM joints. Putty was applied to the clevis joints per STW7-3746, as shown in Figure 6-2, and the joints were mated. After mating, each joint (Figure 6-3) was inspected from the bore for discontinuities and the putty was tamped.

Nozzle-to-Case Joint Assembly. The putty layup for the nozzle-to-case joint, shown in Figure 1-6, was performed to the dimensions of STW7-3745, as were previous TEMs. Figure 6-4 shows the putty layup used throughout the HPM program. The TEM-7 nozzle was mated to the aft segment with no apparent anomalies. Because of inaccessibility, the nozzle-to-case joint was not inspected or tamped as the field joints were.

Similar to TEM-5 and TEM-6, the nozzle-to-case joint incorporated four vent ports in the fixed housing. The vent ports were left open during assembly to exhaust entrapped air from within the joint. This concept was intended to reduce the potential for O-ring damage from gas flow through putty blowholes.

Prefire Inspection/Joint Putty Tamping. A prefire bore inspection was performed to assess the putty flow/layup of each field joint. The inspection occurred after the chocks were removed and the final leak check had been performed. This did not include the nozzleto-case joint, which was inaccessible during this operation. The putty in the field joints was inspected for grease, discontinuities, bubbles, blowholes, etc.

All volcanoes, bubbles, and possible bubbles were tamped closed with a putty tamping tool. No grease contamination was found in any of the joint putty and the field joint putty condition was nominal. The overall prefire insulation condition of TEM-7 was similar to previous TEMs.

## 6.2.2 Observations

From an insulation standpoint, TEM-7 performed an expected. The performance in all three field joints and nozzle-to-case joint was excellent; no gas penetration to the seals was observed. The joints functioned within the HPM experience.






Figure 6-1. HPM Field Joint

	DOC NO.	TWR-6156	1	VOL
REVISION	SEC		PAGE	30






Figure 6-2. Clevis Joint Filler Putty Layup

DOC NO. TWR-61561 VOL.

SEC PAGE 31

REVISION \_\_\_



REVISION \_\_




Figure 6-3. Assembled HPM Field Joint

DOC NO.	TWR-6156	51	VOL
SEC		PAGE	32




Figure 6-4. TEM-7 (HPM modified) Case-to-Nozzle Joint Configuration-Putty Layup

DOC NO.	TWR-6156	1	VOL	
SEC		PAGE	33	

Postfire Internal Insulation Inspection An internal walkthrough inspection was performed. The internal acreage insulation, center and aft segment NBR inhibitors, and stress relief flaps (center and forward segments) appeared to be in normal condition from the A small amount of castable inhibitor walkthrough inspection. remaining attached to the forward center segment flap. inhibitor remained attached intermittently full circumference to the forward segment flap. Two large pieces of castable inhibitor were found laying loose in the middle of the forward and forward center segments. A more detailed inspection of the flaps and inhibitors was performed when the remaining field joints were The slag pool extended the full length of the aft disassembled. segment and 39 inches into the aft center segment. The size of the slag pool and the amount of slag appeared to be typical of previous static test TEM motors. The final slag weight in the aft segment was 1813 lbs.

Aft Field Joint Insulation The aft field joint was disassembled and inspected on 10 January 1991. The joint insulation and putty were in normal condition showing normal heat effects, charring, and The putty exhibited a constant olive green color with The putty failure at disassembly was 15% adhesive normal tack. (tang side) and 85% cohesive. One terminated blowhole was present at 155 degrees measuring 2.1 inches circumferentially by 0.65 inch radially. The blowhole terminated approximately 0.10 inch inboard of the insulation ramp. The gas penetration was between the tang insulation and the putty. Heat effects with slight erosion to the NBR insulation were present on the tang side of the joint in the region of the blowhole. Heat affected and eroded putty were present on the clevis side. The terminated blowhole is within the experience of the HPM design field joints and had no adverse effect No clevis or tang edge separations were on joint performance. The aft center segment stress relief flap and the aft detected. segment NBR inhibitor were in normal condition. The flap was eroded normally back to the flap bulb full circumference. inhibitor was eroded uniformly showing approximately 8-10 inches remaining. No tears were present on either the flap or inhibitor.

The center field joint was Center Field Joint Insulation disassembled and inspected on 14 January 1991. The joint insulation and putty were in normal condition showing normal heat Gas penetrated into the bondline effects, charring, and erosion. 0.80 inch maximum outboard of the remaining material on the clevis side from 280 deg.-0 deg.-74 deg. Gas did not reach the step in the insulation. The putty exhibited a consistent olive green color with normal tack. The putty failure at disassembly was 2% adhesive No clevis or tang edge separations were and 98% cohesive. The forward center segment stress relief flap and the aft center segment NBR inhibitor were in normal condition. entire flap remained from 270 deg.-0 deg.-90 deg. The NBR inhibitor was eroded uniformly showing approximately 20-25 inches remaining. No tears were present on either the flap or inhibitor. Forward Field Joint Insulation The forward field joint was disassembled and inspected on 16 January 1991. The joint insulation and putty were in normal condition showing normal heat effects, charring, and erosion. Gas penetrated slightly into the joint bondline between the clevis insulation and the putty from 262 The average depth of the gas penetration was 0.30 deg.-280 deg. inch (0.40 inch max.) outboard of the remaining material. affected NBR on the clevis side and heat affected putty on the tang side were present in this region. The putty exhibited a consistent olive green color with normal tack. The putty failure at disassembly was 2% adhesive and 98% cohesive. The tang insulation on this joint had several prefire edge separations over 0.50 inch in axial depth (0.75 inch max). These separations were repaired before joint assembly. No clevis or tang edge separations were detected upon postfire inspection indicating the repair procedure The forward segment stress relief flap and the was adequate. forward center segment NBR inhibitor were in normal condition. entire flap remained full circumference with heat affected and slightly blistered NBR underneath. Castable inhibitor was present The NBR inhibitor was eroded uniformly with intermittently. approximately 25-30 inches remaining. No tears were present on either the flap or inhibitor.

Nozzle-to-Case Joint Insulation The nozzle-to-case joint was disassembled and inspected on 15 January 1991. The joint insulation and putty were in normal condition showing normal heat effects and sooting at the forward edge of the bondline. There was no evidence that gas had penetrated the joint insulation bondline (putty). The putty exhibited a consistent olive green color with normal tack. The putty failure at disassembly was 5% adhesive and 95% cohesive. Three voids in the putty were found on the fixed housing at the step extending forward. The largest void was located at 186 deg. measuring 2.2 inches circumferentially by 0.7 inch axially.

### 6.3 SEALS/LEAK CHECK PERFORMANCE

#### 6.3.1 Introduction

After each pressure vessel joint was assembled, a leak test was performed to determine the integrity of the seals. The leak tests consisted of a joint volume determination and a pressure decay test. The volume and pressure information was combined with temperature and time data, collected during the test, and used in the calculation of a leak rate expressed in terms of standard cubic centimeters per second (sccs). Each leak test has a maximum leak rate allowed.

Some specifications require only a maximum pressure decay over time. This method has been determined as sufficient based on the small, constant volumes, and the equivalent leak rates, which are conservative when using all worst-case variables.

Table 6-1 lists all joints leak tested on TEM-07, corresponding leak test specifications, and the equipment used. The leak tests will be discussed in detail in Section 6.3.1.3. The case factory joints were tested after the original assembly. This report does not discuss the results of those tests. The majority of the nozzle internal joints (joints 1 through 4) were of RSRM configuration and tested to the accompanying requirements. Nozzle internal joint 5 was a combination of HPM and RSRM hardware and could not be leak tested since it only contained a single 0-ring.

Table 6-1. TEM-7 Seal Leak Testing

<u>Joint</u>	Specification	<u>Equipment</u>
Case Field Joints	STW7-3682	8076902
Nozzle-to-Case Joint	STW7-3682	2U129714
Nozzle Joint 1	STW7-3475	8U76248
Nozzle Joint 2	STW7-3476	2U129714
Nozzle Joint 3	STW7-3477	2U129714
Nozzle Joint 4	STW7-3478	2U129714
Ignition System Inner Gasket Outer Gasket	STW7-3632 STW7-3632	2U126714 2U129714
Special Bolt Installation	STW7-3632	2U129714
S&A Joint	STW7-3633	8U76500
Transducer Assembly	STW7-2853	2065686
Barrier-Booster	STW7-2913	2065848

#### 6.3.2 Observations

The case field joint leak test results are shown in Table 6-2. The TEM field joints were tested at lower pressures (185 psig) than RSRM field joints (1,000 psig) because of their configuration. These joints were tested with and without the assembly stands (chocks) in place. This was done since previous HPM motors showed the potential for leaking after the stands were removed. The results of the leak tests for the field joints were acceptable.

The field joint tests were performed with a variation of the 8U75902 Ground Support Equipment leak test system. For testing of the TEM motors, the equipment was modified to include a pressure relief valve to preclude the possibility of over-pressurizing the joint.

Table 6-2. TEM-7 Case Field Joint Leak Test Results

Pressure (psig)	Maximum Leak Rate (sccs)	Actual Leak Ra FWD	ates (sccs), Precl	nock/Postchock AFT
185	0.1	0.0121/ 0.0084	0.0023/ 0.0101	0.0128/ 0.0089
30	0.0082	0.0005/-0.0002	-0.0002/ 0.0000	0.0003/-0.0001

The ignition system leak test results are shown in Table 6-3. The tests were performed with the new leak test equipment as shown in Table 6-1. The equipment was identical to that used to test most of the RSRM joints. All results were within the limits.

Table 6-3. TEM-7 Igniter and S & A Leak Test Results

Joint Seal	Allowable Leak Rate (sccs), HI/LO*	Actual Leak Rate (sccs), HI/LO
Inner	0.10 / 0.0082	0.0043 /-0.0002
Outer	0.10 / 0.0082	0.0070 /-0.0005
Transducer Installation	0.10 / 0.0082	0.0085 /-0.0001
OPT **	10 psi/10 min/ 1 psi/10 min	1.0 / 0.0 2.0 / 0.0 3.0 / 0.0 2.0 / 0.0
Barrier- Booster	1 psi / 10 min	N/A
S & A	0.10 / 0.0082	0.0040 /-0.0001

N/A Not available

<sup>\*</sup> HI = 1000 psig, LO = 30 psig

<sup>\*\*</sup> OPTs tested at 1024 psig and 30 psig, leak rate units are psi/10 min.

Table 6-4 lists the results of the TEM-7 nozzle-to-case joint leak test. This joint was tested at a maximum pressure of 185 psig. This differs from the RSRM nozzle-to-case joint leak tests which are performed at 920 psig. The TEM-7 nozzle-to-case leak test was performed after the first torque sequence, when the axial bolts are torqued to 25 ft.-lb. This procedure prevented the occurrence of a metal-to-metal seal between the fixed housing and the aft dome when the axial bolts were fully torqued. All leak test results were within the allowable limits.

The 2U129714 equipment was used to test the TEM-7 nozzle-to-case joint. This is the new equipment used to test all RSRM nozzle-to-case joints starting with 360L006A.

Table 6-4. TEM-7 Nozzle-to-Case Leak Test Results

Pressure (psig)	Allowable Leak Rate (sccs)	Actual Leak Rate (sccs)
185	0.072	0.0091
30	0.0082	0.0000

The nozzle internal joint leak test results are shown in Table 6-5. The tests were performed with the new leak test equipment as shown in Table 6-1. The equipment was identical to that used to test most of the RSRM joints. All results were within the limits.

Table 6-5. TEM-7 Nozzle Internal Joint Leak Test Results

JOINT #	MAX TEST PRESSURE	*ALLOWABLE LEAK RATE, HI/LO(sccs)	ACTUAL LEAK RATE HI/LO (SCCS)
(# 1)	83	0.029/0.0082	0.0025/0.0006
(#2)	920	0.084/0.0082	0.0007/-0.0003
(#3)	740	0.070/0.0082	0.0010/-0.0008
(#4)	144	0.053/0.0082	0.0032/ 0.0002

#### 6.3.2.1 Forward Field Joint

The TEM-7 forward field joint was disassembled on 16 January 1991. Putty was observed in contact intermittently with the primary O-ring for approximately 60 percent of the joint. Putty in contact with the primary O-ring is a typical condition. The grease on the O-rings and sealing areas was as prescribed in STW7-3688. No anomalous conditions were observed.

#### 6.3.2.2 Center Field Joint

The TEM-7 center field joint was disassembled on 14 January 1991. The condition of the joint was nominal. No hot gas or soot reached the primary O-ring. No damage was found on the primary or secondary O-rings while in the groove. The grease on the O-rings and sealing areas was as prescribed in STW7-3688. Putty was found over the full circumference up to, but not past, the primary O-ring. The leak check plug and port were in nominal condition.

#### 6.3.2.3 Aft Field Joint

The TEM-7 aft field joint was disassembled on 10 January 1991. No hot gas or soot reached the primary O-ring. There was no evidence of damage to the O-rings while in the groove. The grease on the O-rings and sealing areas was as prescribed in STW7-3688. Putty was found in the leak check through hole obstructing all but a very small portion of the hole. Before port hole assessment the joint had shifted approximately 0.5 inch (pinholes were misaligned by approximately 0.5 inch at 0 degrees). The putty apparently extruded into the through hole when the joint shifted because no trace of putty was found on the clevis between the primary and secondary O-rings. A preliminary PFAR was submitted since this condition is outside the engineering limits.

#### 6.3.2.4 Nozzle-to-Case Joint

The TEM-7 nozzle-to-case joint was disassembled on 15 January 1991. Zinc chromate putty was observed up to but not past the primary O-ring around the entire circumference, and no blowholes were observed. Two scratches that could be felt with a 5-mil brass shim stock were found on the aft dome boss secondary sealing surface at 89 degrees and 75.6 degrees. A preliminary PFAR was submitted on the scratches. No other anomalies were observed.

# 6.3.2.5 Internal Nozzle Joint, Forward Exit Cone-to-Aft Exit Cone (Joint 1)

The post-fire evaluation of the TEM-7 aft exit cone-to-forward exit cone joint was conducted on 3 January 1991. The sealing surfaces were visually inspected and found to be in good condition with no evidence of damage, corrosion, or excess grease coverage. No damage was found on the primary or secondary O-rings. RTV backfill was found up to the primary seal but not past the primary O-ring. No pressure path was found through the RTV rubber.

### 6.3.2.6 Igniter

#### 6.3.2.6.1 S&A Removal

The Safety and Arming Device was removed on 17 December 1990. No anomalous conditions were found during the evaluation of the Safe and Arm sealing surfaces and gasket. Heavy soot was found on the gasket aft face, over the full circumference, up to the primary seal. Cadmium plating was missing inward of the gasket aft face primary seal, 0.020 inch from the seal cushion at 175 degrees. No soot was found on the gasket forward face to the primary seal. Heavy soot was found on the retainer inside diameter over the full circumference. No damage to the gasket seals or the Safe and Arm sealing surfaces were found.

### 6.3.2.6.2 S&A Disassembly

The TEM-7 Safe and Arm Device was disassembled on 20 December 1990. One anomalous condition was observed during the disassembly assessment. A small axial scratch was found at 300 degrees on the primary seal surface of the Barrier-Booster (B-B) housing bore. the scratch was less than 0.1 inch in length and could be felt with a 0.005 inch thick brass shim. A preliminary PFAR was submitted on the scratch and presented to the Ignition Team.

Typical soot was observed to reach the rotor shaft forward primary O-ring. Soot was also observed to reach both SII primary O-rings. However, no soot or blow-by was observed past any seal. There was no evidence of damage to the rotor shaft or the SII O-rings.

Typical circumferential galling was found on the land between the primary and secondary seal surfaces of both SII ports. This is an acceptable condition per the barrier-booster refurbishment specification.

## Special Issue (TWR-61209 Paragraph 3.2.3 Item 1)

An assessment was made at disassembly to determine if any contamination was present in the SII port leak test through holes (Ref. DR #400579). No contamination was found.

# 6.3.2.6.3 Igniter Operational Pressure Transducers

No anomalous conditions were found on the OPTs or the O-rings. No damage to the transducer threads or sealing surfaces was found. Each secondary O-ring had typical puncture marks caused by the removal tool.

# .6.3.2.6.4 Igniter Special Bolts

No damage was found on the primary 0-rings and no damage to the bolt threads or sealing surfaces was observed.

# 6.3.2.6.5 Igniter Pressure Transducer

The secondary 0-ring had a typical puncture mark caused by the removal tool. No damage was found on the primary 0-ring. No damage to the plug threads or sealing surfaces was observed.

# 6.3.2.7 Aft End Pressure Transducers

Four aft end pressure transducers on the fixed housing were heat affected. The findings from the heat affected pressure transducers that were presented to the RPRB on 1-9-91 were confirmed in the M-53 Metalography lab. Two of the four primary seals were heat affected which was caused by heating of the transducers and not direct gas impingement. The other two primary seals were not heat affected. The worst case heat affected pressure transducer burned through from inside to outside at the primary O-ring groove. It was also plugged with aluminum slag. No heat effects were found on any secondary O-ring. The secondary O-ring on the aft end OPT type pressure transducer was damaged during assembly due to a grease overfill condition. Details of the lab work will be included in the final report.

Two preliminary PFARs were written. One on the OPT secondary O-ring overfill condition and another on the heat affected primary O-rings on two transducers.

# 6.4 NOZZLE ASSEMBLY PERFORMANCE

## 6.4.1 Introduction

TEM-7 was the first full scale static test for qualification of North American Rayon Corporation (NARC) rayon in all nozzle carbon cloth phenolic (CCP) liners. Two additional full scale nozzles will be statically tested for qualification of the NARC rayon as outlined in the second source rayon program plan, TWR-18965. Low cost nozzle improvements, previously demonstrated on the TEM-6 static test, to be qualified on TEM-7 included a change in the carbon cloth phenolic (CCP) liner ply angle of the cowl, improved inner and outer boot ring phenolic cure cycles, and an improved flexible bearing protector design.

Detailed observations and discussions of nozzle subassemblies and components are contained in the TEM-7 Nozzle Quick-Look Report, TWR-61490. Additional nozzle data will be contained in the TEM-7 Final Test Report, TWR-17659, after all post test nozzle hardware activities and evaluation of data are complete.

## 6.4.2 Observations

# 6.4.2.1 Nozzle Fixed Housing

After the fixed housing phenolic insulation was separated from the metal fixed housing, the phenolic showed char and sooting around each instrumentation through hole on the phenolic to metal bond surface. There were small slag deposits in the immediate vicinity of the holes. The metal housing also was sooted around the holes on the corresponding surfaces. The entire remaining surface which mates with the phenolic insulation was severely rusted. A small area around one hole was cleaned of soot and rust which revealed erosion to the housing. Surface hardness measurements 0.2 inch around is 32  $\rm R_{C}$  and should be 44  $\rm R_{C}$ . Unbond investigation results will be reported in TWR-61585.

The differences between TEM-6 and TEM-7 were:

1. o The TEM-6 fixed housing phenolic insulation was installed during the HPM program.

o The TEM-7 fixed housing phenolic insulation was North American Rayon Corporation (NARC) specifically installed for one of three full scale motor test qualifications.

 o The instrumentation through holes were drilled through the TEM-6 fixed housing and insulation with the phenolic insulation already bonded in place.

On TEM-7 the fixed housing instrumentation holes were drilled through the metal fixed housing without the insulation. The phenolic insulation was then bonded to the fixed housing. After cure of the bondline, the instrumentation holes were drilled through the phenolic insulation.

### 6.4.2.2 Flexible Bearing Protector

Two areas, at 280 degrees and 330 degrees, were burned through the bearing protector. At the 280 degree location, the flex bearing rubber eroded approximately 0.15 inch. Locations from 230 degrees through 0 degree to 10 degrees eroded more than 0.4 inch. The difference between TEM-6 and TEM-7 were:

- o The TEM-6 cowl vent holes were flight configuration, i.e. 5/16 (0.312) inch diameter.
- o The TEM-7 cowl vent holes were increased in size to 3/8 (0.375) inch diameter (Figure 1-7).
- o The belly band region of the TEM-7 bearing protector was increased to 1.0 inch minimum thickness (Figure 1-7).
- o The TEM-7 nozzle was vectored.

#### 6.4.2.3 Internal Joints Backfill

Joint #1 - Aft Exit Cone/Forward Exit Cone Assembly The RTV extended below the char line all the way to the primary O-ring, full depth for 360 degrees. There were no blowpaths present. There were no voids of any significant size.

Joint #2 - Nose Inlet/Cowl Assembly The RTV extended below the char line all the way to the bearing flange, full depth for 360 degrees. The RTV also extruded into the gap intermittently between the bearing flange and the nose cap. There were no blowpaths present. There were no voids of any significant size.

Joint #3 - Nose Inlet/Throat Assembly The RTV extended below the char line all the way to the first 90 degree bend, 75% of the RTV went to the second 90 degree bend. There was one area for about 30 degrees that went past the second bend for about one quarter of an inch. The fill edge was a smooth line, not heavily scalloped. There were no blowpaths present. There were no voids of any significant size.

Joint #4 - Throat/Forward Exit Cone Assembly The RTV extended below the char line the complete circumference of the joint. Scalloping of the RTV was present, with evidence of grease interfering with the flow of RTV into the joint. Grease was found on the phenolics at 22-42, 220-225 and 275-300 degrees. A Postfire Anomaly Record (PFAR) has been written on this condition. The RTV reached the primary O-ring except where grease was present on the phenolics. No blowpaths were present in the RTV. There were no voids of any significant size.

Joint #5 - Aft End Ring/Fixed Housing The RTV reached the O-ring at 210 through 215 degrees. The RTV did extend past the O-ring footprint at 210 degrees on the fixed housing. A PFAR has been written on this condition. It appears that the RTV did not inhibit the sealing action of the O-ring. The only evidence of RTV across footprint was a red stain on the O-ring. No RTV adhered to the fixed housing seal surface. Intermittent voids were present in the RTV from the assembly process but no blowpaths were present. Grease did not interfere with the RTV fill in the joint.

# 6.4.2.4 Internal Joints Conditions

Joint #2 - Nose Inlet/Forward End Ring/Cowl Erosion and heat effect was present on the flex bearing elastomer pad #8 at 280 and 330 degrees. This corresponds to the bearing protector burnthrough areas. An eroded area at 280 degrees measured 0.560 inch long by 0.280 inch wide by 0.160 inch deep. The heat effected area at 330 degrees measured 0.880 inch long by 0.380 inch wide. The erosion and heat effect did not appear to impinge on the surrounding shims.

A light coat of grease was present on the joint metal surfaces except where corrosion was present. Light to medium corrosion was found on the forward face of the forward end ring flange. The corrosion extended from the surface outer edge to the inboard side of the through holes from 348 through 0 to 36 degrees and from 84 to 210 degrees. Minor scratches caused by jacking screws during disassembly were located in four equally spaced locations on the nose-inlet housing aft surface. No bondline separations were observed on this joint.

<u>Joint #3 - Nose Inlet/Throat</u> A light coat of grease was present on the joint metal surfaces. No corrosion or metal damage was observed. No bondline separations were observed on this joint.

Joint #4 - Throat/Forward Exit Cone Assembly Grease coverage on the joint metal surfaces was nominal. No corrosion or damage to the metal components was present. No bondline separations were present on the throat housing assembly. Metal-to-adhesive separations were observed on the forward exit cone assembly. The separation extended the complete circumference of the bondline with a maximum radila width of 0.050 inch.

Joint #5 - Aft End Ring/Fixed Housing Bearing protector burnthrough areas were found at 280 and 330 degrees. A PFAR has been written on this condition. Also, areas of deep erosion were found at 230 through 0 to 90 degrees. The depth of erosion ranged from 0.28 to 0.88 inch. The thickness of the TEM-7 bearing protector was 1.0 inch at the burn-through and eroded areas as compared to the RSRM thickness of 0.75 inch in the same location. The burnthrough and eroded areas were in line with the cowl vent holes.

The diameter of cowl vent holes were enlarged by 0.060 inch for the TEM-7 nozzle.

Grease coverage on the joint metal surfaces was nominal. No corrosion or metal damage was observed. Typical even sooting on the flexible boot inside diameter was present.

No bondline separations were observed at this joint, but the inner boot ring had sheared along the glass plies and moved forward approximately 0.030 inch. The shearing of the ring was associated with the fixed housing insulation separation that was detected at nozzle-to-case demate.

# 6.4.3 TEM-07 Nozzle Strain Gage Response Summary

The TEM-07 nozzle metal parts were RSRM configuration except for the fixed housing which was HPM design. Preliminary review of data from various strain gages indicates expected performance, except for the fixed housing assembly. Also of note is a positive shift of approximately 60 to 130 micro in/in at station 1839.0 (nose inlet assembly) on all four circumferentially located hoop strain gages.

Not all strain data has been evaluate to date. Hoop and meridional stains have been reviewed for gages at the following axial locations:

Station Station	<u>Assembly</u>
1865.0	Forward Exit Cone
1839.39	Throat
1839.0	Nose Inlet
1842.5	Nose Inlet
1867.0	Fixed Housing

Strain data on the forward exit cone and throat were compared to both RSRM predicted values and previously observed actuals. Data showed nominal performance.

Strain data from Station 1842.5 (near the nose inlet housing aft end) on the nose inlet assembly was comparable to previous test measurements. Meridional stain at station 1839.0 was normal and very close to predicted values. The hoop strain at station 1839.0 followed a normal profile except in was shifted in the positive direction approximately 60 to 130 micro in/in. This data is preliminary, and the cause of this shift should be more thoroughly investigated.

Strain data at station 1867.0 on the fixed housing shows an anomalous occurrence at approximately 2 seconds into motor burn. Postfire analysis on this problem is ongoing and will be fully documented in the final test report for TEM-07.

## 6.4.4 Nozzle TVC Performance

The TVC system performed as planned and followed the specified duty cycle.

# 6.5 IGNITION SYSTEM PERFORMANCE

## 6.5.1 Introduction

The SRM ignition system consisted of a modified HPM igniter assembly containing a single nozzle, steel chamber, external and internal insulation, and a solid propellant igniter containing a case bonded 40-point star grain (Figures 6-5 and 6-6). The ignition system was modified with a CO2 quench port.

A Safe and Arm (S&A) device utilizing Krytox grease to lubricate the barrier-booster shaft O-rings was installed on the igniter (Figure 6-7).

## 6.5.2 Observations

<u>S&A Cycle Times</u>. Performance of the Krytox<sup>R</sup> grease on the B-B shaft was excellant. S&A cycle times were within the engineering requirements of 2.0 sec or less at 24 Vdc (TWR-17656 Table III).







Figure 6-5. Ignition System Components and Seals

REVISION \_\_\_\_ DOC NO. TWR-61561 VOL SEC PAGE 49



Standard HPM Igniter System Figure 6-6.

DOC NO.	TWR-6156	1 _	VOL	
SEC		PAGE	50	




Figure 6-7. S&A Device Configuration

DOC NO.	TWR-6156	1	VOL
SEC		PAGE	51

REVISION

#### 6.6 JOINT PROTECTION SYSTEMS PERFORMANCE

#### 6.6.1 Introduction

Field joint heater closeout consisted of cork strips retained with Kevlar straps. The external joint temperatures were sensed by two sensor assemblies mounted adjacent to the heater. Improved field joint heaters (Drawing 1077252), igniter to case joint heater (Drawing 1U77253) and nozzle to case joint heater (Drawing 7U77118) were installed in accordance with Drawing 7U77328. These heaters consisted of redundant, chemically etched, foil circuits which were superimposed upon one another and laminated in polyamide plastic sheets. The underside Kapton surface of the field joint and nozzle to case joint heaters were coated with a pressure sensitive This adhesive provided bonding to the case during adhesive. The lead wires extended from the heaters and were assembly. terminated in electrical connectors.

#### 6.6.2 Observations

The Joint protection systems performed within specifications and maintained the joint temperatures within the required temperature range at the time of motor ignition.

A post-test inspection with the FJPS still on the motor revealed no evidence of damage.

# 6.7 BALLISTICS/MASS PROPERTIES PERFORMANCE

# 6.7.1 Introduction

The SRM propellant, TP-H1148, was a composite type solid propellant, formulated of polybutadiene acrylic acid acrylonitrile terpolymer binder (PBAN), epoxy curing agent, ammonium perchlorate oxidizer and aluminum powder fuel. A small amount of burning rate catalyst (iron oxide) was added to achieve the desired propellant burn rate.

The propellant grain design consists of a forward segment with an eleven point star that transitions into a tapered circular perforated (CP) configuration, two center segment double tapered CP configurations, and an aft segment triple taper CP configuration with a cutout for the partially submerged nozzle.

# 6.7.2 Objectives

The primary test objectives from Section 2.0 regarding ballistics/mass properties were:

- G. Obtain data on the effect of five year storage of loaded SRM case segments upon motor ignition and performance.
- J. Obtain additional data on the low frequency chamber pressure oscillations in the motor forward end and correlate with chamber pressure oscillation measurements in the motor aft end.
- K. Obtain additional data on chamber pressure drop down the bore by the use of aft end pressure transducers.

# 6.7.3 Conclusions/Recommendations

The TEM-7 ballistic performance was within expected limits. The TEM-7 ballistic performance compared well with previous TEM performance and HPM historical data. The aft end pressure gauges provided very little useful ballistics data due to the aft end anomalous condition. The five year storage of loaded case segments did not appear to effect motor performance. The measured slag weight in the aft segment was 1813 lbm.

The TEM-7 motor exhibited chamber pressure oscillations similar to previously tested Space Shuttle HPMs. The 1-L mode oscillations were typical for an HPM. In general, HPM 1-L mode amplitudes are lower than those for RSRMs. The magnitudes of the TEM-7 oscillations were among the lowest experienced in HPMs. The aft end pressure oscillations could not be analyzed due to lack of data.

## 6.7.4 Observations

A comparison of TEM-7 performance with predicted values and with the nominal HPM performance revealed few differences. The predicted burn rate for TEM-7 was 0.370 in./sec at 625 psia and 60 °F, the target burn rate was 0.368 in./sec and the delivered burn rate was 0.371 in./sec. Predicted and measured performance compared well and was within the current HPM Specifications.

Table 6-6 is a summary of the measured ballistic and nozzle performance data. Figure 6-8 is a comparison of measured and predicted pressure-time histories. The measured and predicted performance compared well for this motor. Thrust was not measured for this static test, only reconstructed thrust based on nominal thrust to pressure ratios is available.

Figures 6-9 and 6-10 contain plots of the analytical reconstruction of the TEM-7 performance. The analytical model calculated the motor burn rate and Surface Burn Rate Error (SBRE) factor. The calculated burn rate of 0.3709 in./sec at 625 psia and 60 °F was approximately 0.3% above the predicted value of 0.3697, well within burn rate variation. The calculated SBRE table compared well with the nominal HPM table as expected, since the propellant grain geometry was the same.

Figure 6-11 shows measured aft end chamber pressure with reconstructed head-end pressure and the corresponding aft-end pressure data. The reconstruction is forced to match the head-end pressure, not aft end pressure. The TEM-6 motor provided good insight to the measured aft end pressure and the reconstructed aft end data shown in Figure 6-11 is believed to be accurate for TEM-7.

The actual TEM-7 aft end pressure data is scattered. At 2 seconds in burn the pressure data rapidly decreases and then recovers to a point. After each gauge recovers from the initial pressure drop, all consistently lag head end pressure. Post flight inspection did reveal plugged port holes and heat affected transducers. As shown in the figure, all aft end pressure readings maintained a higher than ambient pressure after the test. Gauge PNNAROO6 drops below the other aft end gauges as was seen on TEM-6.

The ballistics code shows the reconstruction of PSN to be higher than actual measured data, but the reconstruction of pressure at axial location 1577 in. (aft segment factory joint) is very close to measured aft-end pressure. The ballistics model is a 1-D code that does not accurately model the flow field in the aft end of the aft segment (the 1-D model shows a pressure recovery after location 1577 in.). Previous strain gauge data has shown no increase in pressure in this region and thus the pressure at the factory joint models the aft end pressure very well.

THIOKOL CORPORATION SRM STATIC TEST TEM-7 11 DECE	DECEMBER 1990 S	
_ 0.21	- 11 - 2L	DEG F
MEASURED MEAN BOLK TEMPERATURE MEASURED MEAN PRESSURE	65,00 12,28	DEG F PSIA
A METSAT DATA		
TATEL PARCE PROPERTANT VEIGHT	1109826.0	LBS
TOTAL EXPENDED WEIGHT	1114116 2000,0 2000,0	LB3
EXPENDED THERE WEIGHT	718.0	1.05
A TOWNAND SECRETAL  B TOWNAND CENTER SECRENT	598.0 962.0	LBS
C AFT SEGRENT THREE NOZZLE  D AFT SEGRENT THREUDING NOZZLE  FROM FIFT D JOINT FORMARD)	4072.0	183
F TOTAL EXPENDED INERTS	6350.0	1.85
TOTAL EXPENDED PROPELLANT WEIGHT	1107826.0	183
		- 1
	2280,3	į
INITIAL THROAT AREA	24.9.3	NI DS
WEB TIME AVERAGE THROAT AREA	6.5 82	l
TOTAL TIME AVERAGE THROAT AREA	5.982	1
DATEM EVIT AREA	176 1.8	- 1
TOTAL TIME AVERAGE EXIT AREA	1/6:4.4	
WEB TIME AVERAGE THROAT RADIAL EXOSION RATE	0.00310	i
TOTAL TIME AVERAGE THROAT RADIAL EROSION RATE	7.773	1
LES TIME AVERAGE EXPANSION RATIO	7,4138	
ACTION TIME AVERAGE EXPANSION RATIO	0.97292	
ACTION TIME AVERAGE MOZZLE EFFICIENCY		
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	

•

THICKOL CORPORATION SRN STATIC TEST TEM-7 11 DB  THICKOL CORPORATION SRN STATIC TEST TEM-7 11 DB  THICK THE STATE THAT THAT THE STATE THAT THAT THE STATE THAT THAT THAT THAT THAT THAT THAT	DECEMBER 1990 S  0.023  0.023  0.023  0.023  0.023  0.023  120,951  120,951  120,952  120,952  120,952  120,952  120,952  120,952  120,952  120,952  120,952  120,952  120,953  123,065  16,504  16,504  16,504  16,504  16,504  16,504  16,504  16,504  16,504  16,504  16,504  16,504  17,506  18,005  18,00	SEC SEC SEC SEC SEC SEC SEC SEC SEC SEC

.,

\*\*\* 01\*\*\*

THURCOL CORPORATION SENS STATES THE THE THE STATES THAT THE PRESENCE TO MACHINE THE STATES THAT THE THAT THAT
---

\*\*\*\* 02\*\*\*

TWR-61561 Page 58

122.1

\*\*\*D 02\*\*\*

701 202-1

TWR-61561 Page 59

\*\*6 02\*\*\*

THINKIN CARPORATION SICH STATIC TEST TEN-7 11 DECEMBER 1990 S	
TO 90, DEGREES	
D. TIME AND BALLISTIC DATA  BECKELIBE  D. 026  SEC	
722.0	
INDICATION OF HEAD END PRESSURE	
WEB TIME 116.931 SEC ACTION TIME 961.12 PSIA	VI.
HEAD END PRESSURE  3483113.  ST. CORRECTED TO VACUUM	T
PRESSURE 700.99	PSIA
683.77 RE 635.08	SIA
in I	
67,820	MILLION LB-SEC
626 692	
267,232	
RRECTED TO VACUUM 267, 231	SEC SEC
401°997 W	
561	

TWR-61561 Page 60

TEM—7 Predicted and Measured Pressure at 65 Deg. F Measured **Predicted** 120 100 110 90 80 60 **Time** ( 50 300-200-100-006 1,0001 700-400-800-009 500 Pressure (psia)

TWR-61561 Page 61

100 110 120 130 TEM—7 Reconstructed and Measured Pressure at 65 Deg. F - Reconstructed Measured 90 80 9 50 40 30 20 1,0001 200-600 <del>]</del> 400-100-800-300--006 700-500 Pressure (psia)

120 130 Deg. 65 100 110 TEM—7 Reconstructed Vacuum Thrust at 90 80 Time (sec) 09 50 40 30 1,500,000 √ ) 2,500,000<u>→</u> 500,000 Thrust 2,000,000 1,000,000 3,500,000 3,000,000

TWR-61561 Page 63

110 120 130 TEM—7 Comparison of Reconstructed and Measured Aft—End Pressure 100 90 80 Time (sec. 9 50 REC. AFT PRES. 40 **PNNAR5A PNNAR6A** PNNAR4A **PNNAR3A** 30 **AVGPH** 20 200-800 Pressure (psia)

TWR-61561 Page 64

All aft end gauges were acoustically quiet (due to partial plugging) and no oscillation analysis could be made.

The motor average subscale burn rates, full-scale motor burn rates (determined from post-test curve matching) and resulting scale factors for SRM-15 to SRM-24, used to predict the TEM-7 burn rate are listed in Table 6-7. The full-scale motor burn rates were determined form post-test curve matching in which the analytical model was forced to match the measured motor performance. The mean scale factor was 1.0175 with a sigma 0.00440 and a coefficient of variation of 0.432 percent.

A plot of the measured data comparing the ignition transients of the TEM static tests is shown in Figure 6-12. The TEM-7 transient was very similar to previously measured motor ignition performance. The TEM-7 maximum pressure rise rate was 80.62 psi/10-msec. The historical three point average pressure rise rate is 90.07 psi/10-msec with a variation of 6.80 psi/10-msec. TEM-7 was the second lowest measured pressure rise rate but was within 2 standard deviations from the population average. A summary table showing the historical pressure rise rates, thrust rise rates and ignition intervals is shown in Table 6-8. A summary of the TEM-7 ignition events is shown in Table 6-9.

The TEM-7 igniter grain configuration was identical to the HPM flight and static test igniter design. The igniter was cast from propellant batch number D760006 using TP-H1178 propellant. The delivered maximum mass flow rate was 330.0 lbm/sec at 65 °F for the TEM-7 igniter (65 °F is the assumed PMBT for the igniter). The TEM-7 igniter performance characteristics were within the expected ranges. Comparison of the TEM-7 igniter performance at 80 °F with the igniter limits at 80 °F is shown in Figure 6-13. The TEM-7 is within the limits at 80 °F.

A comparison of the igniter pressure versus motor head-end and nozzle stagnation pressure for the first 1.4 seconds of motor operation is shown in Figure 6-14. The slight mismatch between igniter and head-end chamber pressure values from 0.6 to 1.4 seconds is within allowed transducer error. A plot of head-end and nozzle stagnation pressure for the full duration of the static test is shown on Figure 6-15. These curves are characteristic of the ratio of the head-end to nozzle stagnation pressures from previous SRM static test motors.

Table 6-7. Burn Rate Data Comparison Subscale to Full-Scale

AT 625 PSIA, 60 °F

SRM   5" CP   SRM   SRM   STD.   PRED.   DEL.   STD.			BURN RAT	E	•	SCALE FACTOR
STM_15A	•	CDM		SRM		
SRM-15A 0.368 0.366 0.370 0.3701 1.0112  SRM-15B 0.368 0.366 0.370 0.3709 1.0134  SRM-16B 0.368 0.365 0.369 0.3684 1.0093  SRM-16B 0.368 0.365 0.369 0.3688 1.1040  SRM-17B 0.368 0.365 0.367 0.3680 1.0138  SRM-17B 0.368 0.362 0.366 0.3694 1.0204  SRM-17B 0.368 0.362 0.366 0.3693 1.0202  SRM-18A 0.368 0.362 0.366 0.3693 1.0202  SRM-19B 0.368 0.363 0.368 0.3690 1.0165  SRM-19B 0.368 0.364 0.369 0.3703 1.0173  SRM-19B 0.368 0.364 0.369 0.3704 1.0176  SRM-20B 0.368 0.366 0.371 0.3744 1.0230  SRM-20B 0.368 0.366 0.371 0.3744 1.0230  SRM-21A 0.368 0.366 0.371 0.3744 1.0230  SRM-21B 0.368 0.365 0.368 0.371 0.3744 1.0258  SRM-22B 0.368 0.365 0.368 0.3744 1.0258  SRM-22B 0.368 0.362 0.365 0.367 0.3703  SRM-22B 0.368 0.362 0.365 0.3675 1.0512  SRM-22B 0.368 0.364 0.367 0.3701 1.0213  SRM-23B 0.368 0.364 0.367 0.3713 1.0201  SRM-23B 0.368 0.364 0.367 0.3721 1.0223  SRM-23B 0.368 0.364 0.367 0.3721 1.0223  SRM-23B 0.368 0.364 0.367 0.3721 1.0223  SRM-24B 0.368 0.366 0.367 0.3721 1.0223  SRM-24B 0.368 0.366 0.367 0.3721 1.0223  SRM-24B 0.368 0.360 0.366 0.3677 1.0217  SRM-24B 0.368 0.360 0.366 0.3677 1.0217  SRM-24B 0.368 0.360 0.366 0.3677 1.0214  DM-9 0.368 0.360 0.366 0.3667 0.3691 1.0196  DM-9 0.368 0.360 0.366 0.3667 1.0181  DM-9 0.368 0.360 0.366 0.3667 1.0215  DM-9 0.368 0.360 0.366 0.3667 1.0215  DM-9 0.368 0.360 0.366 0.3667 1.0214  DM-9 0.368 0.360 0.366 0.3667 1.0214  DM-9 0.368 0.360 0.366 0.3667 1.0215  DM-9 0.368 0.360 0.366 0.3667 1.0215  DM-9 0.368 0.360 0.368 0.3664 1.0196  DM-7 0.368 0.360 0.368 0.3669 1.0116  DM-8 0.368 0.360 0.368 0.3667 1.0215  DM-9 0.368 0.360 0.366 0.3667 1.0215  DM-9 0.368 0.360 0.368 0.3669 1.0116  DM-9 0.368 0.360 0.366 0.3667 1.0160  DM-9 0.368 0					DEL.	STD.
SRM-15A 0.368 0.366 0.370 0.3709 1.0134 SRM-15B 0.368 0.366 0.369 0.3694 1.0093 SRM-16A 0.368 0.365 0.369 0.3688 1.1040 SRM-16B 0.368 0.365 0.369 0.3688 1.1040 SRM-17A 0.368 0.365 0.367 0.3690 1.0138 SRM-17A 0.368 0.362 0.366 0.3694 1.0204 SRM-17B 0.368 0.362 0.366 0.3693 1.0202 SRM-18B 0.368 0.362 0.368 0.3690 1.0165 SRM-19A 0.368 0.364 0.369 0.3703 1.0173 SRM-19A 0.368 0.364 0.369 0.3704 1.0176 SRM-19B 0.368 0.364 0.369 0.3704 1.0176 SRM-20B 0.368 0.366 0.371 0.3744 1.0230 SRM-20B 0.368 0.366 0.371 0.3744 1.0230 SRM-21A 0.368 0.366 0.367 0.370 0.3737 1.0183 SRM-21B 0.368 0.366 0.367 0.370 0.3737 1.0123 SRM-22B 0.368 0.362 0.365 0.368 0.3744 1.0258 SRM-22B 0.368 0.362 0.365 0.3675 1.0152 SRM-22B 0.368 0.364 0.367 0.371 1.0201 SRM-23B 0.368 0.364 0.367 0.371 1.0223 SRM-22B 0.368 0.364 0.367 0.371 1.0223 SRM-22B 0.368 0.364 0.367 0.371 1.0223 SRM-22B 0.368 0.364 0.367 0.3721 1.0223 SRM-23B 0.368 0.364 0.367 0.3721 1.0223 SRM-24B 0.368 0.364 0.367 0.3721 1.0223 SRM-24B 0.368 0.366 0.365 0.3678 1.0177 SRM-24B 0.368 0.360 0.366 0.3674 1.0177 SRM-24B 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3667 1.0191 DM-9 0.368 0.360 0.366 0.3667 1.0215 DM-9 0.368 0.360 0.366 0.3667 1.0196 DM-9 0.368 0.360 0.360 0.366 0.3667 1.0196 DM-9 0.368 0.360 0.36	MOTOR	TARGET				4 0110
SRM-15B	151	0 269	0.366	0.370		
SRM-16A 0.368 0.365 0.3669 0.3684 1.0000 SRM-16B 0.368 0.365 0.365 0.367 0.3688 1.1040 SRM-17A 0.368 0.363 0.367 0.3680 1.0138 SRM-17B 0.368 0.362 0.366 0.3694 1.0204 SRM-17B 0.368 0.362 0.366 0.3694 1.0202 SRM-18B 0.368 0.362 0.367 0.3693 1.0202 SRM-18B 0.368 0.368 0.369 0.3703 1.0173 SRM-19B 0.368 0.364 0.369 0.3703 1.0173 SRM-19B 0.368 0.364 0.369 0.3704 1.0176 SRM-19B 0.368 0.364 0.369 0.3704 1.0176 SRM-20A 0.368 0.368 0.364 0.369 0.3704 1.0176 SRM-20B 0.368 0.366 0.371 0.3744 1.0230 SRM-21B 0.368 0.366 0.371 0.3744 1.0230 SRM-21B 0.368 0.365 0.365 0.367 0.3702 0.3737 1.0183 SRM-21B 0.368 0.365 0.365 0.3657 1.0152 SRM-22B 0.368 0.362 0.365 0.3675 1.0152 SRM-22B 0.368 0.362 0.365 0.3675 1.0213 SRM-23B 0.368 0.364 0.367 0.3713 1.0201 SRM-23B 0.368 0.364 0.367 0.3713 1.0201 SRM-24B 0.368 0.368 0.364 0.367 0.3713 1.0201 SRM-24B 0.368 0.368 0.364 0.367 0.3713 1.0221 SRM-24B 0.368 0.366 0.366 0.3677 0.3721 1.0223 SRM-24B 0.368 0.368 0.366 0.3665 0.3678 1.0177 SRM-24B 0.368 0.368 0.360 0.365 0.3678 1.0177 SRM-24B 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3665 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3667 1.0181 DM-9 0.368 0.360 0.366 0.3667 1.0181 DM-9 0.368 0.360 0.366 0.3667 1.0215 DM-7 0.368 0.360 0.366 0.3667 1.0215 DM-7 0.368 0.360 0.366 0.3667 1.0214 DM-9 0.368 0.360 0.366 0.3667 1.0214 DM-9 0.368 0.360 0.366 0.3667 1.0215 DM-9 0.368 0.360 0.366 0.3667 1.0215 DM-9 0.368 0.360 0.360 0.366 0.3667 1.0214 DM-9 0.368 0.360 0.360 0.366 0.3667 1.0214 DM-1 0.368 0.362 0.368 0.3664 1.0122 TEM-2 0.368 0.362 0.368 0.3664 1.0122 TEM-3 0.368 0.362 0.368 0.3667 1.0166 TEM-1 0.368 0.362 0.368 0.3667 1.0166 TEM-4 0.368 0.362 0.368 0.3667 1.0166 TEM-5 0.368 0.362 0.366 0.3667 1.0166 TEM-6 0.368 0.362 0.368 0.360 0.3667 1.0166 TEM-6 0.368 0.362 0.364 0.370 0.3701 1.0165				0.370		
SRM-16B 0.36B 0.365 0.3669 0.3680 1.0138 SRM-17A 0.368 0.363 0.367 0.3680 1.0138 SRM-17B 0.368 0.362 0.366 0.3694 1.0204 SRM-17B 0.368 0.362 0.366 0.3693 1.0202 SRM-18A 0.368 0.362 0.366 0.3693 1.0202 SRM-18B 0.368 0.363 0.368 0.3690 1.0165 SRM-19B 0.368 0.364 0.369 0.3703 1.0173 SRM-19B 0.368 0.364 0.369 0.3704 1.0176 SRM-20A 0.368 0.368 0.364 0.369 0.3704 1.0176 SRM-20B 0.368 0.368 0.366 0.371 0.3744 1.0230 SRM-21A 0.368 0.366 0.371 0.3744 1.0238 SRM-21A 0.368 0.365 0.366 0.371 0.3744 1.0258 SRM-22B 0.368 0.365 0.365 0.3675 1.0152 SRM-22B 0.368 0.362 0.365 0.3675 1.0152 SRM-22B 0.368 0.362 0.365 0.3675 1.0213 SRM-23A 0.368 0.364 0.367 0.3713 1.0201 SRM-23B 0.368 0.364 0.367 0.3721 1.0223 SRM-24A 0.368 0.366 0.364 0.367 0.3721 1.0223 SRM-24B 0.368 0.366 0.366 0.3675 1.0177  AVERAGE SCALE FACTOR = 1.0175, SIGMA = 0.00440, %CV = 0.432  ETM-1 0.368 0.365 0.366 0.3665 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3665 0.3677 1.0214 DM-9 0.368 0.368 0.360 0.366 0.36577 1.0215 DM-7 0.368 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.368 0.360 0.366 0.36577 1.0215 DM-7 0.368 0.368 0.360 0.366 0.3657 1.0160 DTEM-1 0.368 0.362 0.368 0.3659 1.0116 DTEM-1 0.368 0.362 0.368 0.3657 1.0215 DTEM-2 0.368 0.362 0.368 0.3657 1.0215 DTEM-3 0.368 0.362 0.368 0.3657 1.0215 DTEM-4 0.368 0.362 0.368 0.3667 1.0160 DTEM-4 0.368 0.362 0.368 0.3667 1.0166 DTEM-4 0.368 0.362 0.368 0.3667 1.0166 DTEM-4 0.368 0.362 0.368 0.3667 1.0166 DTEM-6 0.368 0.366 0.3667 0.3700 1.0166 DTEM-6 0.368 0.368 0.366 0.3667 0.3700 1.0166				0.369		
SRM-17A 0.368 0.363 0.367 0.3680 1.0204 SRM-17B 0.368 0.362 0.366 0.3694 1.0204 SRM-18A 0.368 0.362 0.367 0.3693 1.0202 SRM-18B 0.368 0.368 0.362 0.367 0.3693 1.0202 SRM-19B 0.368 0.368 0.363 0.368 0.3690 1.0165 SRM-19B 0.368 0.364 0.369 0.3703 1.0173 SRM-19B 0.368 0.364 0.369 0.3704 1.0176 SRM-20A 0.368 0.368 0.364 0.369 0.3704 1.0176 SRM-20B 0.368 0.368 0.366 0.371 0.3742 1.0168 SRM-20B 0.368 0.366 0.371 0.3744 1.0230 SRM-21B 0.368 0.365 0.368 0.370 0.3737 1.0183 SRM-21B 0.368 0.365 0.368 0.370 0.3737 1.0183 SRM-21B 0.368 0.365 0.368 0.3744 1.0258 SRM-22B 0.368 0.365 0.365 0.3675 1.0152 SRM-22B 0.368 0.362 0.365 0.3697 1.0213 SRM-23B 0.368 0.362 0.365 0.3697 1.0213 SRM-23B 0.368 0.364 0.367 0.3713 1.0201 SRM-23B 0.368 0.364 0.367 0.3713 1.0201 SRM-24B 0.368 0.360 0.365 0.3678 1.0217 SRM-24B 0.368 0.360 0.365 0.3678 1.0217 SRM-24B 0.368 0.360 0.365 0.3674 1.0177 SRM-24B 0.368 0.360 0.365 0.3677 1.0214 DM-8 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3677 1.0215 DM-9 0.368 0.360 0.366 0.3667 1.0215 DM-9 0.368 0.360 0.366 0.3667 1.0215 DM-9 0.368 0.360 0.366 0.3667 1.0215 DM-1 0.368 0.360 0.366 0.3667 1.0215 DM-2 0.368 0.360 0.366 0.3667 1.0215 DM-1 0.368 0.360 0.366 0.3667 1.0215 DM-1 0.368 0.360 0.366 0.3667 1.0215 DM-2 0.368 0.360 0.366 0.3667 1.0215 DM-1 0.368 0.360 0.366 0.3667 1.0215 DM-2 0.368 0.360 0.366 0.3667 1.0215 DM-1 0.368 0.360 0.366 0.3667 1.0215 DM-2 0.368 0.360 0.366 0.3667 1.0215 DM-3 0.368 0.360 0.366 0.3667 1.0215 DM-1 0.368 0.360 0.360 0.366 0.3667 1.0215 DM-2 0.368 0.360 0.360 0.366 0.3667 1.0215 DM-3 0.368 0.360 0.366 0.3667 1.0215 DM-4 0.368 0.360 0.362 0.368 0.3664 1.0122 DM-5 0.368 0.360 0.366 0.3667 1.0116 DM-7 0.368 0.360 0.362 0.368 0.3667 1.0116 DM-9 0.368 0.360 0.360 0.366 0.366				0.369		
SRM-17B 0.368 0.362 0.366 0.3694 1.0204 SRM-17B 0.368 0.362 0.367 0.3693 1.0202 SRM-18A 0.368 0.362 0.367 0.3693 1.0202 SRM-18B 0.368 0.363 0.368 0.3690 1.0165 SRM-19B 0.368 0.364 0.369 0.3703 1.0173 SRM-19B 0.368 0.364 0.369 0.3704 1.0176 SRM-20B 0.368 0.368 0.364 0.369 0.3704 1.0168 SRM-20B 0.368 0.366 0.371 0.3742 1.0168 SRM-20B 0.368 0.366 0.371 0.3744 1.0230 SRM-21A 0.368 0.365 0.366 0.371 0.3744 1.0238 SRM-21B 0.368 0.365 0.368 0.3744 1.0258 SRM-21B 0.368 0.365 0.365 0.3675 1.0152 SRM-22B 0.368 0.362 0.365 0.3675 1.0152 SRM-22B 0.368 0.362 0.365 0.3675 1.0213 SRM-22B 0.368 0.364 0.367 0.3713 1.0201 SRM-23A 0.368 0.364 0.367 0.3713 1.0201 SRM-24A 0.368 0.364 0.367 0.3721 1.0223 SRM-24B 0.368 0.360 0.365 0.3678 1.0217 SRM-24B 0.368 0.360 0.365 0.3678 1.0217 SRM-24B 0.368 0.361 0.366 0.3677 1.0217 SRM-24B 0.368 0.360 0.365 0.3677 1.0217 SRM-24B 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3667 1.0216 DM-1 0.368 0.360 0.366 0.3667 1.0216 DM-2 0.368 0.360 0.366 0.3667 1.0214 DVM-1 0.368 0.360 0.368 0.3667 1.0215 DM-1 0.368 0.360 0.368 0.3664 1.0122 DM-2 0.368 0.360 0.368 0.3667 1.0215 DM-3 0.368 0.360 0.366 0.36677 1.0214 DVM-1 0.368 0.362 0.368 0.3664 1.0122 DM-2 0.368 0.362 0.368 0.3667 1.0215 DM-3 0.368 0.362 0.368 0.3664 1.0122 DM-4 0.368 0.362 0.368 0.3664 1.0122 DM-5 0.368 0.362 0.368 0.3664 1.0122 DM-6 0.368 0.362 0.368 0.3664 1.0122 DM-7 0.368 0.362 0.368 0.3664 1.0122 DM-8 0.368 0.362 0.368 0.3664 1.0125 DM-9 0.368 0.362 0.368 0.3664 1.0125 DM-9 0.368 0.362 0.368 0.3667 1.0166 DM-9 0.368 0.362 0.368 0.3667 1.0166 DM-9 0.368 0.369 0.366 0.3667 1.0166 DM-9 0.368 0.369 0.360 0.3666 0.3667 1.0166 DM-9 0.368 0.369 0.360 0.3666 0.3667 1.0166 DM-9 0.368 0.369 0.360 0.3666 0.3667 1.0166 DM-9 0.368 0.369 0.360 0.366 0.3667 1.0166 DM-9 0.368 0.369 0.369 0.369 0.3690 0.3666 0.3667 1.0166				0.367		
SRM-18A						
SRM-18B				0.367		
SRM-19A						
SRM-19B						
SRM-20A						
SRM-20B 0.368 0.366 0.371 0.3744 1.0230 SRM-20B 0.368 0.367 0.370 0.3737 1.0183 SRM-21A 0.368 0.367 0.370 0.3737 1.0183 SRM-21B 0.368 0.365 0.368 0.365 0.368 0.3744 1.0258 SRM-21B 0.368 0.362 0.365 0.3675 1.0152 SRM-22A 0.368 0.362 0.365 0.3697 1.0213 SRM-23B 0.368 0.364 0.367 0.3713 1.0201 SRM-23A 0.368 0.364 0.367 0.3721 1.0223 SRM-23B 0.368 0.364 0.367 0.3721 1.0223 SRM-23B 0.368 0.364 0.367 0.3721 1.0223 SRM-24A 0.368 0.360 0.365 0.3678 1.0217 SRM-24B 0.368 0.361 0.366 0.3674 1.0177 SRM-24B 0.368 0.361 0.366 0.3674 1.0177 SRM-24B 0.368 0.369 0.366 0.3677 1.0214 DM-8 0.368 0.360 0.366 0.3667 1.0214 DM-9 0.368 0.368 0.360 0.366 0.3665 1.0181 QM-6 0.368 0.368 0.360 0.366 0.3665 1.0181 QM-6 0.368 0.368 0.360 0.366 0.3657 1.0215 QM-7 0.368 0.358 0.360 0.366 0.3677 1.0214 PVM-1 0.368 0.369 0.360 0.366 0.3677 1.0214 DVM-1 0.368 0.369 0.360 0.366 0.3677 1.0214 DVM-1 0.368 0.369 0.360 0.366 0.3677 1.0214 DVM-1 0.368 0.360 0.366 0.3677 1.0214 DVM-1 0.368 0.360 0.366 0.3667 1.0160 DVM-1 0.368 0.362 0.368 0.3659 1.0116 DVM-1 0.368 0.362 0.368 0.3657 1.0155 DVM-1 0.368 0.362 0.368 0.3654 1.0102 DVM-1 0.368 0.362 0.368 0.3664 1.0122 DVM-1 0.368 0.362 0.368 0.3667 1.0165 DVM-5 0.368 0.3667 0.368 0.3667 1.0166 DVM-5 0.368 0.366 0.3667 1.0166 DVM-5 0.368 0.366 0.3667 1.0166 DVM-5 0.368 0.366 0.3667 1.0166 DVM-5 0.368 0.364 0.3667 1.0165 DVM-6 0.368 0.364 0.3667 1.0166 DVM-5 0.368 0.364 0.3667 1.0166 DVM-5 0.368 0.3664 0.3667 1.0166 DVM-5 0.368 0.364 0.3667 1.0165 DVM-5 0.368 0.3664 0.3667 1.0165 DVM-5 0.368 0.36					0.3742	
SRM-21A 0.368 0.367 0.370 0.3737 1.0183 SRM-21B 0.368 0.365 0.3668 0.3714 1.0258 SRM-22B 0.368 0.362 0.365 0.3675 1.0152 SRM-22B 0.368 0.362 0.365 0.3697 1.0213 SRM-23B 0.368 0.364 0.367 0.3713 1.02213 SRM-23B 0.368 0.364 0.367 0.3721 1.0223 SRM-24B 0.368 0.364 0.365 0.3678 1.0217 SRM-24B 0.368 0.360 0.365 0.3678 1.0177  AVERAGE SCALE FACTOR = 1.0175, SIGMA = 0.00440, %CV = 0.432  ETM-1 0.368 0.360 0.366 0.3677 1.0214 DM-8 0.368 0.360 0.366 0.366 0.3677 1.0214 DM-9 0.368 0.360 0.366 0.3665 1.0181 QM-6 0.368 0.360 0.366 0.3665 1.0181 QM-7 0.368 0.360 0.366 0.3665 1.0181 QM-7 0.368 0.360 0.366 0.3665 1.0181 QM-7 0.368 0.360 0.366 0.3657 1.0215 QM-7 0.368 0.360 0.366 0.3657 1.0215 DM-9 0.368 0.360 0.366 0.3657 1.0215 DM-9 0.368 0.360 0.366 0.3667 1.0121 TEM-1 0.368 0.362 0.368 0.3659 1.0116 TEM-2 0.368 0.362 0.368 0.3659 1.0116 TEM-3 0.368 0.362 0.368 0.3659 1.0116 TEM-4 0.368 0.362 0.368 0.3654 1.0122 TEM-2 0.368 0.362 0.368 0.3654 1.0125 TEM-3 0.368 0.362 0.368 0.3654 1.0125 TEM-4 0.368 0.362 0.368 0.3657 1.0215 TEM-5 0.368 0.362 0.368 0.3657 1.01165 TEM-6 0.368 0.364 0.367 0.3667 1.0166 TEM-6 0.368 0.361 0.367 0.3667 1.0166 TEM-6 0.368 0.364 0.367 0.3670 0.3701 1.0165 TEM-6 0.368 0.364 0.367 0.3700 0.3701 1.0208					0.3744	
SRM-21A 0.368 0.365 0.368 0.367 1.0152 SRM-22A 0.368 0.362 0.365 0.3657 1.0213 SRM-22B 0.368 0.362 0.365 0.3697 1.0213 SRM-22B 0.368 0.364 0.367 0.3713 1.0201 SRM-23A 0.368 0.364 0.367 0.3721 1.0223 SRM-23B 0.368 0.364 0.367 0.3721 1.0223 SRM-24A 0.368 0.360 0.365 0.3678 1.0217 SRM-24B 0.368 0.361 0.366 0.3674 1.0177 SRM-24B 0.368 0.361 0.366 0.3674 1.0177 SRM-24B 0.368 0.361 0.366 0.3674 1.0177 SRM-24B 0.368 0.360 0.366 0.3674 1.0177 SRM-24B 0.368 0.360 0.366 0.3667 1.0214 DR-8 0.368 0.360 0.366 0.3667 1.0196 DM-9 0.368 0.360 0.366 0.3665 1.0181 0.096 0.368 0.360 0.366 0.3665 1.0181 0.096 0.368 0.360 0.366 0.3665 1.0181 0.096 DM-7 0.368 0.360 0.366 0.3667 1.0215 0.007 0.368 0.368 0.360 0.366 0.3667 1.0215 0.007 0.368 0.368 0.360 0.366 0.3667 1.0214 0.368 0.360 0.366 0.3667 1.0215 0.368 0.360 0.366 0.3667 1.0215 0.368 0.362 0.368 0.3664 1.0122 0.368 0.362 0.368 0.3664 1.0122 0.368 0.362 0.368 0.3664 1.0122 0.368 0.362 0.368 0.3664 1.0122 0.368 0.362 0.368 0.3664 1.0122 0.368 0.362 0.368 0.3664 1.0155 0.368 0.362 0.368 0.3667 1.0166 0.368 0.362 0.368 0.3667 1.0165 0.368 0.366 0.3667 1.0165 0.368 0.366 0.3667 1.0165 0.368 0.366 0.3667 1.0165 0.368 0.3664 0.3667 1.0165 0.368 0.368 0.3664 0.370 0.3701 1.0165 0.368 0.3664 0.3667 1.0165 0.368 0.3664 0.3667 1.0165 0.368 0.3664 0.3667 1.0166 0.368 0.3664 0.3667 1.0166 0.368 0.3664 0.3667 1.0166 0.368 0.3664 0.3667 1.0166 0.368 0.3664 0.3667 1.0166 0.368 0.3664 0.3667 1.0166 0.368 0.3664 0.3667 0.3668 0.3667 1.0166 0.368 0.3664 0.3667 0.3668 0.3667 1.0166 0.368 0.3664 0.3667 0.3668 0.3664 0.3667 1.0166 0.368 0.3664 0.3664 0.3667 0.3668 0.3667 1.0166 0.368 0.3664 0.3664 0.3700 0.					0.3737	
SRM-21B					0.3744	_
SRM-22A 0.368 0.362 0.365 0.3697 1.0213 SRM-23A 0.368 0.364 0.367 0.3713 1.02201 SRM-23B 0.368 0.364 0.367 0.3721 1.0223 SRM-23B 0.368 0.368 0.364 0.365 0.3678 1.0217 SRM-24A 0.368 0.360 0.365 0.3678 1.0217 SRM-24B 0.368 0.361 0.366 0.3674 1.0177  AVERAGE SCALE FACTOR = 1.0175, SIGMA = 0.00440, %CV = 0.432  ETM-1 0.368 0.365 0.366 0.3677 1.0214 DM-8 0.368 0.360 0.366 0.3677 1.0214 DM-9 0.368 0.362 0.368 0.3691 1.0196 DM-9 0.368 0.360 0.366 0.3665 1.0181 QM-6 0.368 0.360 0.366 0.3665 1.0181 QM-7 0.368 0.358 0.364 0.3657 1.0215 QM-7 0.368 0.360 0.366 0.3677 1.0214 PVM-1 0.368 0.360 0.366 0.3657 1.0215 TEM-1 0.368 0.360 0.366 0.3659 1.0116 TEM-1 0.368 0.362 0.368 0.3659 1.0116 TEM-1 0.368 0.362 0.368 0.3659 1.0116 TEM-2 0.368 0.362 0.368 0.3664 1.0122 TEM-2 0.368 0.362 0.368 0.3672 1.0155 TEM-3 0.368 0.362 0.368 0.3672 1.0155 TEM-4 0.368 0.362 0.368 0.3672 1.0155 TEM-5 0.368 0.362 0.368 0.3667 1.0166 TEM-6 0.368 0.361 0.367 0.3701 1.0165 TEM-6 0.368 0.364 0.370 0.3701 1.0165 FSM-1 0.368 0.364 0.370 0.3701 1.0208					0.3675	
SRM-22B					0.3697	
SRM-23A					0.3713	
SRM-23B       0.368       0.360       0.365       0.3678       1.0217         SRM-24B       0.368       0.361       0.366       0.3674       1.0177         AVERAGE SCALE FACTOR = 1.0175, SIGMA = 0.00440, %CV = 0.432         ETM-1       0.368       0.365       0.372       0.3681       1.0085         DM-8       0.368       0.360       0.366       0.3677       1.0214         DM-9       0.368       0.362       0.368       0.3691       1.0196         QM-6       0.368       0.360       0.366       0.3657       1.0215         QM-7       0.368       0.358       0.364       0.3657       1.0215         QM-7       0.368       0.360       0.366       0.3677       1.0214         PVM-1       0.368       0.362       0.368       0.3659       1.0116         TEM-2       0.368       0.362       0.368       0.3664       1.0122         TEM-3       0.368       0.362       0.368       0.3672       1.0155         TEM-5       0.368       0.362       0.369       0.3681       1.0160         TEM-6       0.368       0.361       0.367       0.370       0.3701       1.0165 <td></td> <td></td> <td></td> <td></td> <td>0.3721</td> <td></td>					0.3721	
SRM-24A	SRM-23B				0.3678	
AVERAGE SCALE FACTOR = 1.0175, SIGMA = 0.00440, %CV = 0.432  ETM-1	SRM-24A					1.0177
AVERAGE SCALE FACTOR = 1.0175,	SRM-24B	0.368	0.361	0.566		
ETM-1 0.368 0.365 0.365 0.367 1.0214  DM-8 0.368 0.360 0.366 0.3691 1.0196  DM-9 0.368 0.360 0.366 0.3665 1.0181  QM-6 0.368 0.360 0.366 0.3657 1.0215  QM-7 0.368 0.358 0.364 0.3657 1.0214  PVM-1 0.368 0.360 0.366 0.3677 1.0214  PVM-1 0.368 0.362 0.368 0.3659 1.0116  TEM-1 0.368 0.362 0.368 0.3664 1.0122  TEM-2 0.368 0.362 0.368 0.3672 1.0155  TEM-3 0.368 0.362 0.368 0.3672 1.0155  TEM-4 0.368 0.362 0.369 0.3681 1.0160  TEM-5 0.368 0.362 0.368 0.3654 1.0105  TEM-6 0.368 0.361 0.367 0.3667  TEM-6 0.368 0.364 0.370 0.3701 1.0165  FSM-1 0.368 0.363	AVERAGE	SCALE FACTOR	R = 1.0175,	SIGMA = 0.00440,	%CV = 0.432	
ETM-1       0.368       0.360       0.366       0.3677       1.0214         DM-8       0.368       0.362       0.368       0.3691       1.0196         DM-9       0.368       0.360       0.366       0.3665       1.0181         QM-6       0.368       0.358       0.364       0.3657       1.0215         QM-7       0.368       0.360       0.366       0.3677       1.0214         PVM-1       0.368       0.360       0.368       0.3659       1.0116         TEM-1       0.368       0.362       0.368       0.3664       1.0122         TEM-2       0.368       0.362       0.368       0.3672       1.0155         TEM-3       0.368       0.362       0.368       0.3681       1.0160         TEM-4       0.368       0.362       0.369       0.3681       1.0105         TEM-5       0.368       0.362       0.368       0.3654       1.0105         TEM-6       0.368       0.364       0.370       0.3701       1.0165         FSM-1       0.368       0.364       0.370       0.3709       1.0208		0.000	0 365	0.372		
DM-8 DM-9 O.368 O.362 O.368 O.360 O.366 O.3655 OM-6 O.368 O.368 O.360 O.364 O.3657 OM-7 O.368 O.360 O.366 O.3657 O.3677 O.368 O.360 O.366 O.3677 O.368 O.369						
DM-9       0.368       0.360       0.366       0.3657       1.0181         QM-6       0.368       0.358       0.364       0.3657       1.0215         QM-7       0.368       0.358       0.366       0.3677       1.0214         PVM-1       0.368       0.360       0.368       0.3659       1.0116         TEM-1       0.368       0.362       0.368       0.3664       1.0122         TEM-2       0.368       0.362       0.368       0.3672       1.0155         TEM-3       0.368       0.362       0.368       0.3681       1.0160         TEM-4       0.368       0.362       0.368       0.3654       1.0105         TEM-5       0.368       0.361       0.367       0.3667       1.0166         TEM-6       0.368       0.364       0.370       0.3701       1.0165         FSM-1       0.368       0.363       0.370       0.3709       1.0208						
QM-6       0.368       0.358       0.364       0.3657       1.0215         QM-7       0.368       0.360       0.366       0.3677       1.0214         PVM-1       0.368       0.360       0.368       0.3659       1.0116         TEM-1       0.368       0.362       0.368       0.3664       1.0122         TEM-2       0.368       0.362       0.368       0.3672       1.0155         TEM-3       0.368       0.362       0.369       0.3681       1.0160         TEM-4       0.368       0.362       0.368       0.3654       1.0105         TEM-5       0.368       0.361       0.367       0.3667       1.0166         TEM-6       0.368       0.364       0.370       0.3701       1.0165         FSM-1       0.368       0.363       0.370       0.3709       1.0208						
QM-/       0.368       0.360       0.366       0.3677       1.0214         PVM-1       0.368       0.362       0.368       0.3659       1.0116         TEM-1       0.368       0.362       0.368       0.3664       1.0122         TEM-2       0.368       0.362       0.368       0.3672       1.0155         TEM-3       0.368       0.362       0.369       0.3681       1.0160         TEM-4       0.368       0.362       0.368       0.3654       1.0105         TEM-5       0.368       0.361       0.367       0.3667       1.0166         TEM-6       0.368       0.364       0.370       0.3701       1.0165         FSM-1       0.368       0.363       0.370       0.3709       1.0208						
TEM-1 0.368 0.362 0.368 0.3659 1.0116 TEM-2 0.368 0.362 0.368 0.3664 1.0122 TEM-3 0.368 0.362 0.368 0.3672 1.0155 TEM-4 0.368 0.362 0.369 0.3681 1.0160 TEM-5 0.368 0.362 0.368 0.3654 1.0105 TEM-6 0.368 0.361 0.367 0.3667 1.0166 TEM-6 0.368 0.364 0.370 0.3701 1.0165 FSM-1 0.368 0.363 0.364 0.370 0.3709 1.0208						
TEM-1 0.368 0.362 0.368 0.3664 1.0122 TEM-2 0.368 0.362 0.368 0.3672 1.0155 TEM-3 0.368 0.362 0.369 0.3681 1.0160 TEM-4 0.368 0.362 0.369 0.3654 1.0105 TEM-5 0.368 0.362 0.368 0.3654 1.0105 TEM-6 0.368 0.361 0.367 0.3667 1.0166 TEM-6 0.368 0.364 0.370 0.3701 1.0165 FSM-1 0.368 0.363 0.364 0.370 0.3709 1.0208						
TEM-2 0.368 0.362 0.368 0.3672 1.0155 TEM-3 0.368 0.362 0.369 0.3681 1.0160 TEM-4 0.368 0.362 0.368 0.3654 1.0105 TEM-5 0.368 0.362 0.368 0.3654 1.0166 TEM-6 0.368 0.361 0.367 0.3667 1.0165 FSM-1 0.368 0.364 0.370 0.3701 1.0165 FSM-1 0.368 0.363 0.364 0.370 0.3709 1.0208						
TEM-3 0.368 0.362 0.369 0.3681 1.0160 TEM-4 0.368 0.362 0.368 0.3654 1.0105 TEM-5 0.368 0.362 0.367 0.3667 1.0166 TEM-6 0.368 0.361 0.370 0.3701 1.0165 FSM-1 0.368 0.364 0.370 0.3709 1.0208						
TEM-4 0.368 0.362 0.368 0.3654 1.0105 TEM-5 0.368 0.361 0.367 0.3667 1.0166 TEM-6 0.368 0.364 0.370 0.3701 1.0165 FSM-1 0.368 0.363 0.370 0.3709 1.0208						
TEM-5 0.368 0.361 0.367 0.3667 1.0166 TEM-6 0.368 0.364 0.370 0.3701 1.0165 FSM-1 0.368 0.364 0.370 0.3709 1.0208						
TEM-6 0.368 0.364 0.370 0.3701 1.0165 FSM-1 0.368 0.364 0.370 0.3709 1.0208						
FSM-1 0.360 0.370 0.3709 1.0208						
TEM-7 0.368 0.300					0.3709	1.0208
	TEM-7	0.368	0.505			

Table 6-8. Historical Three Point Average Thrust and Pressure Rise Rate Data


MOTOR	OCCURRENCE TIME	PRESSURE RISE RATE	OCCURRENCE TIME	THRUST RISE RATE	IGNITION INTERVAL
STATIC TEST DM-2 QM-1 QM-2 QM-3 QM-4 ETM-1A DM-8 DM-9 QM-6 QM-7 PVM-1 TEM-01 QM-8 TEM-2 TEM-3 TEM-4 TEM-5 TEM-6 FSM-1	0.1480 0.1560 0.1640 0.1560 0.1505 0.1520 0.1680 0.1640 0.1480 0.1480 0.1520 0.1520 0.1520 0.1520 0.1520 0.1520 0.1520 0.1520	85.30 86.38 93.58 94.45 91.96 86.72 77.00 81.00 87.40 99.60 92.80 85.13 72.30 94.40 88.51 81.52 87.12 84.49 97.06	0.1480 0.1560 0.1720 0.1520 0.2225 0.1560 0.1760 0.1720 0.1520 N/A 0.1520 0.1520 N/A 0.1520 N/A 0.1520 N/A 0.1520 N/A 0.1520 0.1520 0.1520 0.1520	245,380 246,128 234,950 245,615 234,438 230,023 257,272 275,525 211,476 N/A 294,664 238,583 N/A 288,772 N/A 279,764 N/A 273,946 250,453	0.2330 0.2362 0.2391 0.2287 0.2192 0.2279 0.2424 0.2436 0.2321 0.2230 0.2338 0.2255 0.2517 0.2280 0.2272 0.2283 0.2299 0.2342 0.2278
FLIGHT MOTORS SRM-1A SRM-1B SRM-2A SRM-2B SRM-3A SRM-3B SRM-5A SRM-5B SRM-6A SRM-6B SRM-7A SRM-7B SRM-7B SRM-10A SRM-10B SRM-10B SRM-13B RSRM-1A RSRM-1B RSRM-1A RSRM-1B RSRM-1B RSRM-2A RSRM-2B	0.1530 0.1500 0.1530 0.1660 0.1500 0.1530 0.1660 0.1530 0.1470 0.1500 0.1530 0.1500 0.1530 0.1530 0.1500 0.1530 0.1530 0.15500 0.1530 0.15500 0.15500 0.15501	87.58 91.57 90.74 90.27 91.05 89.68 95.10 84.43 92.72 88.22 99.90 99.32 106.29 91.06 92.31 92.89 84.56 98.85 99.0 80.5 87.3 100.2			0.2373 0.2358 0.2348 0.2345 0.2308 0.2271 0.2361 0.2380 0.2342 0.2329 0.2224 0.2276 0.2224 0.2196 0.2303 0.2373 0.2342 0.2310 0.2390 0.2342
STANDA % COEFFICIENT	NUMBER AVERAGE ARD DEVIATION OF VARIATION			11 246,732 22,627 9.17	35 0.2321 0.0076 3.27
TEM-7	0.1600	80.62	N/A	N/A	0.2359

Table 6-9. Measured SRM Ignition Performance Data at 65 °F

		SPECIFICATION
PARAMETER	TEM-7	REQUIREMENT
MAXIMUM IGNITER MASS FLOW RATE (LBM/SEC)	330.0	N/A
IGNITION TRANSIENT (SEC) (0 TO 563.5 PSIA)	0.2359	0.170 - 0.340
MAXIMUM PRESSURE RISE RATE (PSI/10-MSEC)	80.6	109
PRESSURE LEVEL AT START OF MAXIMUM RISE RATE (PSIA)	231	N/A
TIME SPAN OF MAXIMUM PRESSURE RISE (MSEC)	160 - 170	N/A
EQUILIBRIUM PRESSURE 0.6 SEC (IGNITION END) (PSIA)	931	N/A
TIME TO FIRST IGNITION (SEC) (BEGIN PRESSURE RISE)	0.029	N/A

.500 .450 Measured Head-End Pressure Transients TEM-3 TEM-4 - TEM-2 TEM-7 .400 TEM-5 . TEM-6 .... TEM-1 .350 0 .250 .300 Time (sec) .200 .150 .100 .050 000 100--009 500-400-1,0007 200 300 006 800-700 Pressure (psia)

TWR-61561 Page 69



TWR-61561 Page 70

1.40 - PSN1, Nozzle Stagnation Pressure TEM-7 Igniter Pressure vs. Head-End and Nozzle Stagnation Pressure 1.20 PNCAC005, Igniter Pressure AVGPH, Chamber Pressure 1.00 .80 Time (sec) 9. .20 00. Pressure 8000 2,0007 (psia) 1,200-1,600-200-1,800-1,400--009 400-

TWR-61561 Page 71

100 110 120 130 PSN1, Nozzle Stagnation Pressure TEM-7 Measured Head-End and Nozzle Stagnation Pressure Time Histories AVGPH, Chamber Pressure 80 Time (sec) 9 50 40 30 10 100-2007 -0091,0007 <del>1006</del>  $500^{-}$ 400-300-800-700-Pressure (psia)


TEM-7 was instrumented with 3 pressure transducers for head-end pressure measurement (PNCACO01-PNCACO03) and 1 gauge for igniter pressure measurement (PNCACO05). The signal from the head-end OPT data channel (PNCACO01) was split to provide both A-C coupled data (for chamber pressure oscillation data) and mean pressure. TEM-7 was also instrumented with 4 aft end pressure gauges (PNNARO03-PNNARO06) and again the aft end OPT data channel (PNNARO06) was split to provide both oscillatory aft end chamber pressure data and mean data. However, aft end data was not useful for dynamic analysis on this test. In addition, the mean pressure data channels are used to calculate dynamic pressure and to verify the accuracy of the A-C coupled data.


Data acquired from gauge PNCAC001 are displayed in a waterfall plot format in Figure 6-16. The first longitudinal (1-L) and second longitudinal (2-L) acoustic modes can be observed at about 15 and 30 Hz, respectively. This waterfall plot is fairly typical of HPM designs. The magnitudes on this static test were among the lowest experienced on HPMs.

Figures 6-10 and 6-11 describe the running, instantaneous, peak-to-peak oscillation amplitudes of the 1-L and 2-L acoustic modes respectively for the TEM-7 motor head-end pressure. This type of analysis is more representative of instantaneous oscillations than are the time averaged oscillations presented in a waterfall plot.


When using waterfall plots to compare static test motor oscillation amplitudes, it is important to remember that this format uses an averaging method of analysis. This presents no difficulty for steady state signals but has an attenuating effect on transient signals. Since most of the data obtained from a solid rocket motor are transient, any oscillation magnitudes referred to as maxima are, in fact, not true but averaged values over a given time slice. These numbers are, nonetheless, very useful for comparison. Table 6-10 shows such a comparison for recent static test motors and the flight motors. This table contains the most recent data. DM-6 and DM-7 were Filament Wound Case (FWC) motors.

A comparison of TEM-7 thrust data at 60 °F and a burn rate of 0.368 in./sec at 625 psia and 60 °F with the CEI Specification CPW1-3300, dated 15 January 1986, thrust-time limits at 0.368 in./sec is shown on Figure 6-19. The TEM-7 performance was within average population limits. Note that the limits are for the average of the historical SRM population not an individual motor. The historical motor population is well within the limits. None of the individual motor performance tolerances and limit parameters were exceeded. The TEM-7 ignition performance satisfied the ignition interval and the maximum pressure rise rate requirements as shown in Table 6-9.





PRESSURE (PSI P-P)



PRESSURE (PSI P-P)

Compared to CEI Specification Limits TEM-7 Reconstructed Thrust




Table 6-10 MAXIMUM PRESSURE OSCILLATION AMPLITUDE COMPARISON

можов	SOURCE OF MEASUREMENT	MODE	TIME OF MEASUREMENT	FREQUENCY (HZ)	MAX PRESSURE (PSI 0-T0-PEAK)
MOTOR	Waterfall	1-L	85	15.5	0.45
TEM-7	PNCAC002	2-L	100	29.5	0.53
FSM-1 *	Waterfall	1-L	100	14.0	0.64
	PNCAC001	2-L	79	29.5	0.74
TEM-6	Waterfall PNCACO01	1-L 2-L	92 98/99	15.0 29.5	$0.41 \\ 0.67$
TEM-6	Waterfall	1-L	92	15.0	0.31
(Aft)	PNNAR005	2-L	98/99	29.5	
TEM-5	Waterfall	1-L	81	16.0	0.46
	PNCAC005	2-L	100	29.5	0.57
TEM-4	Waterfall	1-L 2-L	115 87	14.5 29.5	0.37 0.96
TEM-3	Waterfall	1-L 2-L	106 102	15.0 30.0	0.36 0.58
STS-29	Waterfall	1-L	86	15.5	0.31
(left)	AC OPT	2-L	89	28.0	0.44
STS-29	Waterfall	1-L	85	15.5	0.38
(right)	AC OPT	2-L	83	29.5	0.54
TEM-2	Waterfall	1-L 2-L	78 100	16.0 29.5	0.43 0.68
QM-8 *	Waterfall	1-L	104	14.5	1.32
	(P000002)	2-L	55	27.5	0.47
TEM-1	Waterfall	1-L 2-L	79 95	15.5 29.5	0.37 0.78
STS-27	Waterfall	1-L	82	15.5	0.37
(left)	AC OPT	2-L	82	29.5	0.60
STS-27	Waterfall	1-L	82	15.5	0.57
(right)	AC OPT	2-L	83	29.5	0.72
STS-26	Waterfall	1-L	79	16.0	0.70
(left)	AC OPT	2-L	95	29.5	0.87
STS-26 (right)	Waterfall	1-L	83	15.0	0.54
	AC OPT	2-L	94	30.0	0.47
PVM-1 *	Waterfall	1-L 2-L	99 79	14.5 29.5	$\frac{1.23}{0.77}$
QM-7 *	Waterfall	1-L	93	14.5	1.40
	P000001	2-L	79	29.5	0.95
QM-6 *	Waterfall	1-L 2-L	107 85	14.5 29.5	1.05 0.53

<sup>\*</sup> RSRM static test motors.

<sup>\*\*</sup> Filament wound case (FWC) HPM motors.

Table 6-10 (cont)
MAXIMUM PRESSURE OSCILLATION AMPLITUDE COMPARISON

MOTOR	SOURCE OF MEASUREMENT	MODE	TIME OF MEASUREMENT	FREQUENCY (HZ)	MAX PRESSURE (PSI 0-T0-PEAK)
DM-9 *	Waterfall	1-L 2-L	107 96	14.5 30.0	0.81 0.64
DM-8 *	Waterfall	1-L 2-L	78 97	16.0 29.5	0.58 0.62
ETM-1A	Waterfall	1-L 2-L	84 101	15.5 29.5	0.45 0.61
DM-7 **	Waterfall	1-L 2-L	77 96	15.5 29.0	0.90 0.62
DM-6 **	Waterfall	1-L 2-L	76 86	15.5 29.0	0.51 0.78
QM-4	Waterfall	1-L 2-L	81 80	15.5 29.5	0.31 0.30

<sup>\*</sup> RSRM static test motors.

<sup>\*\*</sup> Filament wound case (FWC) HPM motors.

## 6.8 STATIC TEST SUPPORT EQUIPMENT

## 6.8.1 Introduction

The deluge system and related instrumentation were similar to previous TEMs. Deluge system nozzle arrangement is shown in Figure 1.2.8-1.

## 6.8.2 Observations

The deluge system performed as designed.

## 7.0 APPLICABLE DOCUMENTS

Drawings	<u>Title</u>
Unnumbered	TEM-7 Drawing Tree
1U50159	Plug, Leak Check Port, Nozzle
1050185	Case Segment, Stiffener
1U50188	Transducer, Motional Pickup Pressure
1U50776	Igniter, Rocket Motor, Test Configuration
1U51055	Pin Straight Headless
1051899	Retainer, Pin Field Joint, SRM
1U51927	Gasket - Outer
1U52295	S/A Device
1U52565	Segment, Rocket Motor, Fwd (Thermal Protection)
1U52566	Segment, Rocket Motor, Center (Thermal Protection)
1U52757	Segment, Rocket Motor, Aft (Thermal Protection)
1U52840	Flex Bearing Assembly
1U76425	Adjustable Vent Port Plug
1U76598	Bolt, Machine, Ultrasonic
1U76702	Cable Assembly, Power, Electrical- Heater, Fwd Dome
1U76703	Cable Assembly, Power, Electrical, Branched-Heater, Fwd Segment
1U76704	Cable Assembly, Power, Electrical, Branched-Heater, Fwd Ctr Segment
1U76705	Cable Assembly, Power, Electrical, Branched-Heater, Aft Ctr Segment

1076706	Cable Assembly, Power, Electrical- Heater, Aft Segment
1U77252	Heater - Field Joint
1U77253	Heater - Igniter to Case Joint
1U82840	Band Pin Assembly Retainer
1U100269	Plug, Machine Thread
2U65040	Assembly Fixture - Nozzle
2U129361	CO <sub>2</sub> Quench System T-97
2U129363	Water Deluge System
2U129760	Static Test Arrangement
2U129764	Aft Test Stand Ass'y Sequence T-97
2U129765	Forward Test Stand Sequence
4U69505	Shield, Deluge System
7U76608	Boot Assy, Flexible Bearing, Nozzle
7U76609	Cowl, Flexible Boot, Nozzle
7076736	Exit Cone Assy, Fwd Section
7076738	Nozzle Assembly, Final
7076827	Boot Cavity Pressure Transducer Assy
7U76864	Bearing Protector, Flexible
7076865	Housing Assembly, Modified - Nozzle, Fixed $\cdot$
7076879	Test Assembly, TEM
7U76881	Motor Assy, Test, TEM
7U76882	Nozzle Assembly Segment, TEM
7076899	Igniter/Fwd Segment Assy, TEM
7076902	Transducer Assy, Pressure
7076983	Insulated SAPMD

7077118	Heater - Field Joint, Nozzle and Igniter, Refurbished
7U77266	Nose Inlet Assembly
7U77267	Exit Cone Assy, Aft - Modified
7U77310	Throat - Inlet Assy, Nozzle
7077328	Joint Protection Systems, Technical Evaluation Motor
Specifications	<u>Title</u>
CPW1-3600A	Prime Equipment Contract End Item Detail Specification (CEI)
STW4-2621	Insulation, Acrylonitrile Butadiene Rubber (NBR), Asbestos and Silicon Dioxide-Filled
STW4-2868	Thermal Insulation, Ethylene Propylene Diene Monomer (EPDM) - Neoprene Rubber, Carbon Fiber - Filled
STW4-3266	Putty and Caulking or Glazing Compounds, Other
STW4-3339	Rubber, Fluorocarbon, Elastomer; High Temperature and Compression Set Resistant
STW5-2833	TP-H1178 Propellant, Solid Rocket Motor, Igniter Space Shuttle Project
STW5-3223	Inhibitor, UF-3267, Solid Rocket Motor, Space Shuttle Projects
STW5-3224	Liner, Solid Rocket Motor, Space Shuttle Project.
STW5-3343	Propellant, Solid Rocket Motor, TP-H1148
STW7-2831 No Change	Inspection and Process Finalization Criteria, Insulated Components, Space Shuttle Solid Propellant Rocket Motor
STW7-2853	Leak Test, Pressure Transducer Assemblies, Space Shuttle Project SRM

STW7-2913	Procedure, Leak Test of Barrier-Booster Redundant Seals
STW7-3475	Leak Testing, Forward-to-Aft-Exit-Cone Joint, Space Shuttle Redesigned Solid Rocket Motor
STW7-3476	Leak Testing, Forward-End-Ring-to-Nose- Inlet Housing Joint, Space Shuttle Redesigned Solid Rocket Motor
STW7-3477	Leak Testing, Nose-Inlet-to-Throat Support Housing Joint, Space Shuttle Redesigned Solid Rocket Motor
STW7-3478	Leak Testing, Throat-Support-Housing- to-Forward-Exit-Cone Joint, Space Shuttle Redesigned Solid Rocket Motor
STW7-3632	Leak Test, Inner and Outer Igniter Joints, Space Shuttle Project Solid Rocket Motor
STW7-3633	Leak Test, S & A
STW7-3682	Leak Testing, Field and Case to Nozzle Joints
STW7-3688	Grease Application and O-Ring Installation, Field and Case to Nozzle Joints
STW7-3745	Putty, Aft Segment and Nozzle Assembly Joint, Application of
STW7-3746	Putty, Vacuum Seal, Field Joint Assembly, Application of
Documents	<u>Title</u>
TWR-17656	TEM-07 Flash Report
TWR-17659	Technical Evaluation Motor No. 6 (TEM-6) Final test Report
TWR-18965	Program Plan for Development and Qualification of a Second Source Rayon Supplier (1650 Denier)
TWR-19121	Predicted Ballistic Performance Characteristics for TEM-7

TWR-19524B	Program Plan for Low Cost Nozzle Improvements
TWR-19838	Technical Evaluation Motor 7 (TEM-07) Performance Information Summary
TWR-60273	TEM Postfire Engineering Evaluation Plan
TWR-60857	Cowl Vent Hole Diameter Study and TEM-2 Nozzle Boot Cavity Pressurization
TWR-61209	Postfire Hardware Special Issues TEM-7
TWR-61231	TEM-7 Seals Squeeze and Temperature Requirements
TWR-61490	TEM-7 Nozzle Quick-Look Report
TWR-61585	TEM-07 Fixed Housing Unbond Investigation